



木曽川氾濫ブロック分割

様式 - 2

資産データ

水系名:木曾川

河川名:木曾川

国勢調査平成17年

事業所統計調査平成18年

区块 ブロック	ブロック 面積 (ha)	一般資産等基礎数量																	一般資産額(百万円)								農作物資産(百万円)			一般資産 額 等合計 (百万円)	備考				
		人口 (人)	世帯数 (戸)	従業者数(人)														農漁家数 (世帯)	延床面積 (ha)	水田面積 (ha)	畑面積 (ha)	事業所資産		農漁家資産		小計	水稲	畑作物	小計						
				鉱業	建設業	製造業	電気等	情報通信	運輸・通信	卸売小売	金融・保険	不動産	飲食店	医療	教育	複合	サービス					公務	償却	在庫	償却							在庫			
L1	10285.70	141,025	44,439	0	3,783	12,681	178	159	4,288	11,303	657	710	3,823	6,134	2,663	684	6,297	1,705	2,196	838.90	4274.30	767.40	1,485.976	707.771	208.071	113.852	5,253	1,229	2,522.152	4,735	238	4,973	2,527.125		
L2	1889.10	8,160	1,912	0	239	968	11	0	68	283	1	5	160	240	101	50	161	106	658	54.10	1075.40	233.50	94.319	34.590	9,477	5,985	1,576	369	146,316	1,193	75	1,268	147,584		
L3	22581.70	648,145	218,370	6	16,646	58,443	780	940	13,262	52,540	3,957	2,794	19,797	21,639	10,771	2,150	26,291	4,046	5,751	2957.90	5438.80	2965.90	5,288.533	3,392.631	870.153	506.647	13,754	3,218	10,074.936	6,034	951	6,985	10,081.921		
L4	414.10	8,804	2,480	0	138	1,427	0	4	120	186	8	6	65	168	149	20	352	35	19	49.90	0.10	29.40	84.758	39.807	10,523	7,753	47	11	142,899	0	90	90	142,989		
L5	4681.40	135,671	43,559	0	3,174	12,288	141	67	2,510	8,519	423	257	4,077	4,703	2,386	458	3,827	202	736	632.40	764.20	874.90	1,131.555	680.570	154,261	93,192	1,760	411	2,061,749	848	280	1,126	2,062,877		
L6	3857.30	131,902	45,438	7	2,822	15,143	106	227	2,208	10,478	739	425	4,644	4,596	2,417	601	5,747	1,382	663	630.20	300.90	686.80	1,127,868	704,022	186,687	113,509	1,585	370	2,134,041	334	220	554	2,134,595		
L7	534.30	13,680	5,056	44	344	4,576	41	8	375	953	45	74	584	928	174	29	914	123	92	50.20	41.80	72.20	85,460	78,821	40,527	26,561	221	52	231,642	45	221	266	231,908		
R1	1688.60	14,740	4,232	5	594	485	15	0	109	506	50	56	232	637	229	121	743	126	349	80.50	705.60	117.10	137,582	69,329	13,962	6,384	836	196	228,289	772	29	801	229,090		
R2	44.20	85	13	0	6	5	0	0	0	1	0	0	0	0	3	0	1	0	0	7	0.70	7.20	15.70	1,155	374	51	43	17	4	1,644	8	5	13	1,657	
R3	1678.70	10,532	2,623	0	426	877	5	1	180	392	4	7	178	320	191	33	265	26	243	74.20	838.10	165.00	123,735	46,040	9,613	6,423	583	136	186,530	895	505	1,400	187,930		
R4	3229.70	73,515	23,934	0	2,148	7,576	43	272	1,631	7,878	458	312	2,728	3,238	1,135	444	3,955	760	469	416.10	888.80	250.30	708,546	378,212	112,342	67,114	1,121	262	1,267,597	949	769	1,718	1,269,315		
R5	62.20	1,017	332	0	37	54	0	0	4	76	0	6	5	24	5	0	38	14	13	7.60	0.80	9.10	13,025	5,322	902	645	32	8	19,934	1	28	29	19,963		
R6	6929.40	232,861	86,925	21	9,845	16,593	288	3,902	7,305	43,333	7,043	2,852	14,260	11,652	6,347	1,565	29,735	7,179	1,126	1288.20	1042.70	426.80	2,194,748	1,342,873	582,088	272,064	2,692	629	4,395,094	1,113	1,310	2,423	4,397,517		
R7	65.30	726	175	0	41	33	0	0	9	41	0	0	83	0	0	0	28	0	0	5.50	0.00	9.10	9,292	2,855	633	371	2	1	13,154	0	28	28	13,182		
R8	3163.90	64,024	21,224	46	1,542	12,342	214	344	1,070	5,839	509	165	2,794	1,806	1,040	339	5,439	2,799	416	330.00	231.50	527.40	561,269	334,416	157,781	81,600	996	233	1,136,294	247	1,613	1,860	1,138,154		
R9	29.50	1,301	480	0	13	28	0	0	11	78	6	3	41	30	7	8	58	0	4	6.10	0.10	1.30	10,408	7,459	893	427	10	2	19,199	0	4	4	19,203		
R10	763.20	19,058	7,122	29	654	2,424	293	40	536	2,488	365	190	1,274	1,490	578	193	2,438	470	134	113.40	29.40	59.80	193,333	111,826	78,368	23,802	322	75	407,726	31	184	215	407,941		
合計	61898.30	1,505,246	508,314	160	42,452	145,941	2,077	5,964	33,686	144,874	14,265	7,822	54,746	57,605	28,196	6,695	86,289	18,973	12,876	7535.90	15639.70	7211.70	13,251,562	7,936,917	2,436,332	1,326,372	30,807	7,206	24,989,196	17,205	6,550	23,755	25,012,951		

様式 - 3	被害額										水系名:木曾川			河川名:木曾川			流量規模:1/200			河道		着手		施設		現ダム
	氾濫ブロック	一般資産被害額		農漁家資産		小計	農作物被害額			公共土木施設等被害額	営業停止損失	家庭における応急対策費用			事業所における応急対策費用	その他の間接被害	小計	合計	備考							
		家屋	家庭用品	事業所資産 償却 在庫	農漁家資産 償却 在庫		水稲	畑作物	小計			清掃労働対価	代替活動等	小計												
L1	69,959	44,089	19,412	6,591	277	90	140,418	711	35	746	237,869	4,972	1,714	2,821	4,535	1,393	0	10,900	389,933							
L2	233,372	147,505	63,381	23,636	1,241	447	469,582	1,531	119	1,650	795,472	13,077	5,302	7,168	12,470	4,629	0	30,176	1,296,880							
L3	430,659	266,788	115,685	48,350	1,963	690	864,135	2,096	317	2,413	1,463,845	24,937	9,504	12,361	21,865	9,111	0	55,913	2,386,306							
L4	40,424	24,162	5,416	2,899	21	6	72,928	0	40	40	123,542	1,163	835	626	1,461	890	0	3,514	200,024							
L5	126,332	84,597	29,914	11,740	125	41	252,749	237	26	263	428,157	8,191	3,394	5,054	8,448	3,566	0	20,205	701,374							
L6	213,209	143,758	67,281	23,395	209	68	447,920	374	97	471	758,777	19,660	7,037	11,104	18,141	7,524	0	45,325	1,252,493							
L7	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0						
R1	109,817	64,260	13,243	5,787	566	159	193,832	286	15	301	328,353	3,772	2,233	1,442	3,675	1,275	0	8,722	531,208							
R2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0						
R3	240,090	157,985	58,639	26,319	606	185	483,824	714	582	1,296	819,599	13,666	5,453	5,153	10,606	6,632	0	30,904	1,335,623							
R4	284,694	192,826	83,022	35,132	664	215	596,553	805	708	1,513	1,010,560	18,626	6,691	6,797	13,488	8,014	0	40,128	1,648,754							
R5	247,417	189,322	134,099	44,592	435	151	616,016	640	572	1,212	1,043,532	33,864	7,563	9,775	17,338	12,691	0	63,893	1,724,653							
R6	350,912	274,418	177,443	61,904	638	220	865,535	882	780	1,662	1,466,216	43,942	10,692	12,883	23,575	17,867	0	85,384	2,418,797							
R7	8,417	2,874	707	386	2	0	12,386	0	15	15	20,983	258	97	61	158	165	0	581	33,965							
R8	17,682	9,293	2,659	1,672	27	8	31,341	8	43	51	53,092	554	309	228	537	320	0	1,411	85,895							
R9	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0						
R10	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0						
合計	1,293,717	821,192	364,933	143,082	3,912	1,288	2,628,124	3,726	1,504	5,230	4,452,042	93,170	32,015	40,368	72,383	37,270	0	202,823	7,288,219							

様式 - 3	被害額										水系名:木曾川			河川名:木曾川			流量規模:1/100			河道		着手		施設		現ダム
	氾濫ブロック	一般資産被害額		農漁家資産		小計	農作物被害額			公共土木施設等被害額	営業停止損失	家庭における応急対策費用			事業所における応急対策費用	その他の間接被害	小計	合計	備考							
		家屋	家庭用品	事業所資産 償却 在庫	農漁家資産 償却 在庫		水稲	畑作物	小計			清掃労働対価	代替活動等	小計												
L1	58,355	36,472	16,184	5,412	227	74	116,724	600	30	630	197,731	4,276	1,470	2,465	3,935	1,198	0	9,409	324,494							
L2	185,498	114,360	49,786	18,037	1,063	380	369,124	1,464	108	1,572	625,295	10,974	4,178	6,101	10,279	3,513	0	24,766	1,020,757							
L3	365,975	228,744	97,815	39,995	1,718	604	734,851	1,832	289	2,121	1,244,837	21,064	8,135	10,855	18,990	7,710	0	47,764	2,029,573							
L4	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0						
L5	94,224	59,255	21,594	8,369	86	28	183,556	193	19	212	310,943	6,349	2,508	3,835	6,343	2,635	0	15,327	510,038							
L6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0						
L7	5,521	3,667	2,535	1,507	14	4	13,248	4	32	36	22,443	738	133	114	247	189	0	1,174	36,901							
R1	106,610	63,519	13,169	5,709	555	156	189,718	286	15	301	321,381	3,678	2,192	1,431	3,623	1,266	0	8,567	519,967							
R2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0						
R3	186,069	121,592	45,318	19,835	496	154	373,464	627	499	1,126	632,649	10,189	4,172	4,190	8,362	4,862	0	23,413	1,030,652							
R4	233,232	158,864	67,857	28,122	560	185	488,820	772	654	1,426	828,061	15,153	5,492	5,938	11,430	6,410	0	32,993	1,351,300							
R5	186,278	139,057	101,684	33,067	325	112	460,523	493	451	944	780,125	26,213	5,628	7,643	13,271	9,353	0	48,837	1,890,429							
R6	260,118	199,514	139,305	46,878	462	161	646,438	679	602	1,281	1,095,063	35,077	7,932	10,167	18,099	13,381	0	66,557	1,809,339							
R7	8,417	2,874	707	386	2	0	12,386	0	15	15	20,983	258	97	61	158	165	0	581	33,965							
R8	14,138	7,811	2,224	1,338	22	7	25,540	7	39	46	43,264	433	255	196	451	260	0	1,144	69,994							
R9	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0						
R10	62,407	46,760	23,444	12,378	114	33	145,136	14	85	99	245,861	6,867	1,705	1,239	2,944	2,855	0	12,666	403,762							
合計	1,004,010	629,341	288,973	116,672	3,465	1,141	2,043,602	3,338	1,412	4,750	3,461,861	73,619	23,741	28,754	52,495	27,711	0	153,825	5,664,038							

様式 - 3	被害額										水系名:木曾川			河川名:木曾川			流量規模:1/77			河道		着手		施設		現ダム
	氾濫ブロック	一般資産被害額		農漁家資産		小計	農作物被害額			公共土木施設等被害額	営業停止損失	家庭における応急対策費用			事業所における応急対策費用	その他の間接被害	小計	合計	備考							
		家屋	家庭用品	事業所資産 償却 在庫	農漁家資産 償却 在庫		水稲	畑作物	小計			清掃労働対価	代替活動等	小計												
L1	54,127	33,328	14,977	4,966	209	67	107,674	554	28	582	182,399	3,984	1,364	2,302	3,666	1,115	0	8,765	299,420							
L2	150,292	91,309	40,044	14,266	935	331	297,177	1,357	99	1,456	503,416	9,295	3,412	5,240	8,652	2,755	0	20,702	822,751							
L3	331,853	206,164	87,578	35,590	1,569	551	663,305	1,703	268	1,971	1,123,638	18,804	7,290	9,866	17,156	6,805	0	42,765	1,831,679							
L4	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0						
L5	85,983	53,095	18,916	7,576	76	25	165,671	178	18	196	280,647	5,788	2,271	3,458	5,729	2,393	0	13,910	460,424							
L6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0						
L7	4,807	3,207	1,887	1,081	12	4	10,998	3	28	31	18,629	563	115	95	210	168	0	941	30,599							
R1	105,299	63,205	13,144	5,677	552	155	188,032	286	15	301	318,526	3,648	2,177	1,427	3,604	1,263	0	8,515	515,374							
R2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0						
R3	151,317	97,585	36,873	15,839	427	133	302,174	572	448	1,020	511,883	8,278	3,361	3,535	6,896	3,819	0	18,993	834,070							
R4	191,829	131,343	56,272	22,838	469	157	402,908	735	607	1,342	682,524	12,405	4,506	5,198	9,704	5,112	0	27,221	1,113,995							
R5	139,306	99,840	73,122	23,947	238	81	336,534	386	377	763	570,088	19,493	4,106	5,835	9,941	6,758	0	36,192	943,577							
R6	199,749	150,951	109,137	36,052	342	119	496,350	471	458	929	840,815	27,974	6,081	8,079	14,160	10,269	0	52,403	1,390,497							
R7	8,273	2,861	706	385	2	0	12,227	0	15	15	20,712	256	96	61	157	165	0	578	33,532							
R8	9,433	5,604	1,733	947	15	5	17,737	6	34	40	30,046	297	180	160	340	187	0	824	48,647							
R9	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0						
R10	47,894	36,135	18,440	9,045	92	27	111,633	12	66	78	189,106	4,803	1,299	1,024	2,323	2,080	0	9,206	310,023							
合計	884,357	548,623	251,031	99,940	3,163	1,042	1,788,156	3,151	1,307	4,458	3,029,135	63,906	20,759	25,662	46,421	23,328	0	133,655	4,955,404							

様式 - 3	被害額										水系名:木曾川			河川名:木曾川			流量規模:1/70			河道		着手		施設		現ダム
	氾濫ブロック	一般資産被害額		農漁家資産		小計	農作物被害額			公共土木施設等被害額	営業停止損失	家庭における応急対策費用			事業所における応急対策費用	その他の間接被害	小計	合計	備考							
		家屋	家庭用品	事業所資産 償却 在庫	農漁家資産 償却 在庫		水稲	畑作物	小計			清掃労働対価	代替活動等	小計												
L1	53,187	32,639	14,722	4,884	204	66	105,702	547	27	574	179,058	3,928	1,340	2,263	3,603	1,099	0	8,630	293,964							
L2	145,588	87,808	38,716	13,720	913	322	287,067	1,339	97	1,436	486,290	9,059	3,306	5,121	8,427	2,657	0	20,143	794,936							
L3	330,833	204,977	87,166	35,406	1,559	548	660,489	1,709	2																	

様式 - 3	被害額														水系名:木曾川		河川名:木曾川		流量規模:1/200			河道		着手		施設		新丸完成
	氾濫ブロック	家屋		家庭用品		一般資産被害額				農作物被害額				公共土木施設等被害額	営業停止損失	家庭における応急対策費用			事業所における応急対策費用	その他の間接被害	小計	合計	備考					
		家屋	家庭用品	事業所資産		農漁家資産		小計	水稲	畑作物	小計	清掃労働対価	代替活動等			小計												
L1	64,842	39,256	17,742	6,009	254	82	128,185	694	33	727	217,146	4,691	1,573	2,641	4,214	1,273	0	10,178	356,236									
L2	202,064	123,328	54,554	20,123	1,108	398	401,575	1,493	109	1,602	680,268	11,623	4,483	6,364	10,847	3,798	0	26,268	1,109,713									
L3	400,969	248,066	106,586	43,816	1,814	640	801,891	1,947	295	2,242	1,358,403	22,501	8,809	11,513	20,322	8,288	0	51,111	2,213,647									
L4	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0								
L5	116,165	76,761	28,407	10,593	112	37	232,075	227	24	251	393,134	7,716	3,138	4,768	7,906	3,309	0	18,931	644,391									
L6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0								
L7	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0								
R1	108,956	64,104	13,234	5,770	565	158	192,787	286	15	301	326,580	3,745	2,221	1,439	3,660	1,272	0	8,677	528,345									
R2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0								
R3	160,651	104,652	39,342	16,917	446	139	322,147	591	468	1,059	545,718	8,815	3,586	3,750	7,336	4,068	0	20,219	889,143									
R4	195,593	132,819	56,316	22,957	486	161	408,332	734	610	1,344	691,714	12,409	4,542	5,211	9,753	5,092	0	27,254	1,128,644									
R5	125,609	91,073	67,451	22,255	218	74	306,680	332	333	665	519,517	17,614	3,707	5,179	8,886	6,169	0	32,669	859,531									
R6	195,234	147,236	106,194	35,336	332	115	484,447	452	444	896	820,654	27,117	5,918	7,830	13,748	10,060	0	50,925	1,356,922									
R7	8,407	2,873	707	386	2	0	12,375	0	15	15	20,963	258	97	61	158	165	0	581	33,934									
R8	8,980	5,316	1,694	909	15	5	16,919	5	32	37	28,658	283	173	157	330	177	0	790	46,404									
R9	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0								
R10	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0								
合計	919,213	561,487	251,567	97,700	3,289	1,086	1,834,342	3,333	1,238	4,571	3,107,378	62,971	21,232	27,117	48,349	23,004	0	134,324	5,080,615									

様式 - 3	被害額														水系名:木曾川		河川名:木曾川		流量規模:1/100			河道		着手		施設		新丸完成
	氾濫ブロック	家屋		家庭用品		一般資産被害額				農作物被害額				公共土木施設等被害額	営業停止損失	家庭における応急対策費用			事業所における応急対策費用	その他の間接被害	小計	合計	備考					
		家屋	家庭用品	事業所資産		農漁家資産		小計	水稲	畑作物	小計	清掃労働対価	代替活動等			小計												
L1	50,092	29,997	13,317	4,430	188	60	98,084	533	26	559	166,152	3,730	1,270	2,176	3,446	1,028	0	8,204	272,999									
L2	139,357	84,156	37,468	13,329	852	301	275,463	1,309	87	1,396	466,635	8,742	3,169	4,929	8,098	2,547	0	19,387	762,881									
L3	324,451	200,906	85,504	34,294	1,499	529	647,183	1,724	254	1,978	1,096,327	18,261	7,096	9,679	16,775	6,544	0	41,580	1,787,068									
L4	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0								
L5	72,930	43,336	16,474	6,385	62	20	139,207	164	17	181	235,817	5,212	1,961	3,083	5,044	2,053	0	12,309	387,514									
L6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0								
L7	1,348	771	264	144	3	1	2,531	3	13	16	4,288	81	27	21	48	30	0	159	6,994									
R1	104,526	63,065	13,135	5,664	551	155	187,096	286	15	301	316,939	3,629	2,167	1,425	3,592	1,263	0	8,484	512,820									
R2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0								
R3	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0								
R4	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0								
R5	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0								
R6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0								
R7	7,466	2,784	688	366	2	0	11,306	0	15	15	19,154	215	90	60	150	164	0	529	31,004									
R8	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0								
R9	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0								
R10	17,810	12,771	5,066	1,988	39	12	37,686	9	33	42	63,840	1,388	454	439	893	647	0	2,928	104,496									
合計	492,989	280,042	106,586	43,661	2,247	745	926,270	2,209	362	2,571	1,569,100	27,160	10,688	13,714	24,402	9,423	0	60,985	2,558,926									

様式 - 3	被害額														水系名:木曾川		河川名:木曾川		流量規模:1/77			河道		着手		施設		新丸完成
	氾濫ブロック	家屋		家庭用品		一般資産被害額				農作物被害額				公共土木施設等被害額	営業停止損失	家庭における応急対策費用			事業所における応急対策費用	その他の間接被害	小計	合計	備考					
		家屋	家庭用品	事業所資産		農漁家資産		小計	水稲	畑作物	小計	清掃労働対価	代替活動等			小計												
L1	45,307	26,812	11,862	3,970	169	54	88,174	492	25	517	149,367	3,418	1,153	1,987	3,140	949	0	7,507	245,565									
L2	126,116	74,260	33,127	11,829	796	278	246,406	1,253	81	1,334	417,412	7,713	2,805	4,452	7,257	2,160	0	17,130	682,282									
L3	298,304	184,377	78,898	31,385	1,394	490	594,848	1,596	241	1,837	1,007,674	17,103	6,561	9,160	15,721	6,056	0	38,880	1,643,239									
L4	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0								
L5	61,030	35,758	12,645	5,204	51	16	114,704	141	15	156	194,308	4,136	1,587	2,462	4,049	1,667	0	9,852	319,020									
L6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0								
L7	1,091	658	228	127	3	1	2,108	3	12	15	3,570	65	23	18	41	28	0	134	5,827									
R1	100,892	62,156	12,980	5,561	538	152	182,279	286	15	301	308,780	3,513	2,124	1,414	3,538	1,245	0	8,296	499,656									
R2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0								
R3	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0								
R4	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0								
R5	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0								
R6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0								
R7	7,165	2,693	684	359	2	0	10,903	0	15	15	18,468	212	87	59	146	162	0	520	29,906									
R8	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0								
R9	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0								
R10	8,218	6,648	2,680	918	17	5	18,486	7	18	25	31,316	819	244	254	498	388	0	1,705	51,532									
合計	457,593	262,166	99,961	40,708	2,156	716	863,300	2,148	337	2,485	1,462,430	25,136	9,933	12,763	22,696	8,743	0	56,575	2,384,790									

様式 - 3	被害額														水系名:木曾川		河川名:木曾川		流量規模:1/70			河道		着手		施設		新丸完成
	氾濫ブロック	家屋		家庭用品		一般資産被害額				農作物被害額				公共土木施設等被害額	営業停止損失	家庭における応急対策費用			事業所における応急対策費用	その他の間接被害	小計	合計	備考					
		家屋	家庭用品	事業所資産		農漁家資産		小計	水稲	畑作物	小計	清掃労働対価	代替活動等			小計												
L1	44,565	26,223	11,615	3,889	165	52	86,509	482	24	506	146,545	3,337	1,122	1,934	3,056	924	0	7,317	240,877									
L2	120,439	70,831	31,496	11,184	777	271	234,998	1,227	79	1,306	398,086	7,349	2,664	4,254	6,918	2,011	0	16,278	650,668									
L3	275,714	167,563	71,841	27,992	1,302	455	544,867	1,513	231	1,744	923,007	15,900	6,027	8,592	14,619	5,563	0	36,082	1,505,700									
L4	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0								
L5	58,033	33,857	11,778	4,906	48	15	108,637	134	14	148	184,032	3,843	1,493	2,303	3,796	1,570	0	9,209	302,026									
L6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0								
L7	1,055	647	223	125	3	1	2,054	3	11	14	3,478	63	22	18	40	28	0	131	5,677									
R1	99,618	61,692	12,956	5,534	529	150	180,479	286	15	301	305,731	3,491	2,107	1,410	3,517	1,242	0	8,250										

氾濫 ブロック	被害額										流量規模:1/200			河道		現況	施設	現ダム		
	水系名:木曾川					河川名:木曾川					公共土木 施設等 被害額	営業停止 損失	家庭における応急対策費用		事業所に おける応 急対策費用				その他 の間接 被害	
	一般資産被害額		農漁家資産		小計	水稲	畑作物	小計	清掃労働 対価	代替 活動等			小計							
家屋	家庭用品	事業所資産 償却	在庫	農漁家資産 償却							在庫									
L1	74,593	47,237	20,807	7,068	296	97	150,098	724	35	759	254,266	5,271	1,832	2,991	4,823	1,513	0	11,607	416,730	
L2	229,388	145,550	62,188	23,137	1,231	443	461,937	1,526	118	1,644	782,521	12,919	5,230	7,099	12,329	4,551	0	29,799	1,275,901	
L3	430,782	267,886	116,209	48,495	1,968	691	866,031	2,112	319	2,431	1,467,058	25,200	9,546	12,481	22,027	9,173	0	56,400	2,391,920	
L4	51,341	28,725	6,988	4,139	24	7	91,224	0	41	41	154,534	1,581	1,000	686	1,686	1,109	0	4,376	250,175	
L5	63,227	37,139	12,433	5,270	53	17	118,139	137	15	152	200,129	4,001	1,607	2,418	4,025	1,683	0	9,709	328,129	
L6	215,658	145,514	68,276	23,776	214	70	453,508	376	98	474	768,241	19,904	7,115	11,212	18,327	7,628	0	45,859	1,268,082	
L7	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
R1	110,953	64,446	13,262	5,811	569	160	195,201	286	15	301	330,670	3,801	2,246	1,444	3,690	1,278	0	8,769	534,941	
R2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
R3	226,201	148,407	55,271	24,605	577	177	455,238	691	564	1,255	771,172	12,727	5,124	4,919	10,043	6,180	0	28,950	1,256,615	
R4	272,683	184,608	79,118	33,377	637	208	570,631	798	696	1,494	966,649	17,796	6,405	6,600	13,005	7,612	0	38,413	1,577,187	
R5	227,405	173,545	125,166	41,128	393	137	567,774	579	524	1,103	961,807	31,619	6,960	9,112	16,072	11,669	0	59,360	1,590,044	
R6	493,707	385,012	229,836	84,843	942	318	1,194,658	1,003	971	1,974	2,023,750	57,915	14,788	16,307	31,095	25,187	0	114,197	3,334,579	
R7	8,417	2,874	708	387	2	0	12,388	0	15	15	20,987	262	97	61	158	165	0	585	33,975	
R8	22,237	11,314	3,439	2,285	32	9	39,316	10	46	56	66,600	735	383	275	658	398	0	1,791	107,763	
R9	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
R10	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
合計	1,292,754	812,288	366,412	143,027	3,913	1,288	2,619,682	3,732	1,527	5,259	4,437,740	95,328	31,977	40,641	72,618	37,435	0	205,381	7,268,062	

氾濫 ブロック	被害額										流量規模:1/100			河道		現況	施設	現ダム		
	水系名:木曾川					河川名:木曾川					公共土木 施設等 被害額	営業停止 損失	家庭における応急対策費用		事業所に おける応 急対策費用				その他 の間接 被害	
	一般資産被害額		農漁家資産		小計	水稲	畑作物	小計	清掃労働 対価	代替 活動等			小計							
家屋	家庭用品	事業所資産 償却	在庫	農漁家資産 償却							在庫									
L1	60,266	37,816	16,826	5,668	235	76	120,887	620	31	651	204,782	4,434	1,516	2,531	4,047	1,243	0	9,724	336,044	
L2	184,309	113,543	49,417	17,852	1,060	378	366,559	1,461	108	1,569	620,951	10,908	4,147	6,067	10,214	3,476	0	24,598	1,013,677	
L3	357,823	223,318	94,739	38,633	1,685	592	716,790	1,787	282	2,069	1,214,241	20,251	7,897	10,550	18,447	7,439	0	46,137	1,979,237	
L4	42,604	25,294	5,727	3,103	22	6	76,756	0	40	40	130,024	1,241	875	641	1,516	941	0	3,698	120,518	
L5	35,881	20,489	6,106	2,814	29	9	65,328	77	10	87	110,666	2,007	822	1,138	1,960	847	0	4,814	180,895	
L6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
L7	5,450	3,615	2,480	1,485	13	4	13,047	4	31	35	22,104	730	132	110	242	188	0	1,160	36,346	
R1	108,021	63,913	13,212	5,747	562	158	191,613	286	15	301	324,592	3,719	2,210	1,436	3,646	1,267	0	8,632	525,138	
R2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
R3	174,404	113,537	42,484	18,559	472	147	349,603	606	483	1,089	592,225	9,543	3,914	3,972	7,886	4,528	0	21,957	964,874	
R4	222,540	151,780	64,409	26,643	538	178	465,998	764	645	1,409	789,400	14,214	5,226	5,736	10,962	6,056	0	31,232	1,288,039	
R5	167,782	123,005	91,300	29,627	291	100	412,085	437	420	857	698,070	23,890	5,034	6,964	11,998	8,344	0	44,232	1,155,244	
R6	369,212	289,354	185,322	65,126	678	234	909,926	903	808	1,711	1,541,415	46,235	11,250	13,372	24,622	18,909	0	89,766	2,542,818	
R7	8,417	2,874	708	387	2	0	12,388	0	15	15	20,987	262	97	61	158	165	0	585	33,975	
R8	20,241	10,339	3,022	1,966	30	8	35,606	9	44	53	60,318	645	349	253	602	362	0	1,609	97,586	
R9	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
R10	56,084	42,483	21,529	11,389	105	31	131,621	13	77	90	222,966	5,968	1,532	1,149	2,681	2,457	0	11,106	365,783	
合計	994,975	618,960	281,185	114,244	3,429	1,127	2,013,920	3,204	1,470	4,674	3,411,582	71,668	23,123	27,328	50,451	27,112	0	149,231	5,579,407	

氾濫 ブロック	被害額										流量規模:1/77			河道		現況	施設	現ダム		
	水系名:木曾川					河川名:木曾川					公共土木 施設等 被害額	営業停止 損失	家庭における応急対策費用		事業所に おける応 急対策費用				その他 の間接 被害	
	一般資産被害額		農漁家資産		小計	水稲	畑作物	小計	清掃労働 対価	代替 活動等			小計							
家屋	家庭用品	事業所資産 償却	在庫	農漁家資産 償却							在庫									
L1	54,645	33,889	15,144	5,022	211	68	108,979	553	28	581	184,610	4,003	1,377	2,317	3,694	1,127	0	8,824	302,994	
L2	148,927	90,181	39,650	14,092	929	328	294,107	1,349	99	1,448	498,216	9,231	3,380	5,208	8,588	2,727	0	20,546	814,317	
L3	312,263	192,533	81,421	32,826	1,481	518	621,042	1,605	256	1,861	1,052,046	17,709	6,846	9,398	16,244	6,361	0	40,314	1,715,263	
L4	33,443	20,862	4,508	2,299	19	6	61,137	0	40	40	103,565	939	716	580	1,296	712	0	2,947	167,689	
L5	26,085	14,678	3,872	1,822	20	6	46,483	52	7	59	78,744	1,284	577	779	1,356	567	0	3,207	128,493	
L6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
L7	4,407	2,829	1,806	1,040	10	3	10,095	3	27	30	17,101	540	103	87	190	160	0	890	28,116	
R1	107,070	63,664	13,178	5,720	557	157	190,346	286	15	301	322,446	3,690	2,198	1,432	3,630	1,267	0	8,587	521,680	
R2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
R3	136,523	87,255	33,407	14,098	401	125	271,809	554	423	977	460,445	7,498	2,994	3,237	6,231	3,325	0	17,054	750,285	
R4	183,876	126,144	54,280	21,874	448	150	386,772	726	596	1,322	655,193	11,972	4,319	5,064	9,383	4,870	0	26,225	1,069,512	
R5	110,083	78,912	58,924	19,044	192	65	267,220	273	303	576	452,671	15,553	3,223	4,649	7,872	5,304	0	28,729	749,196	
R6	297,156	231,576	156,097	53,517	522	180	739,048	716	646	1,362	1,251,948	39,045	9,132	11,300	20,432	15,453	0	74,930	2,067,288	
R7	8,417	2,874	707	387	2	0	12,387	0	15	15	20,984	260	97	61	158	165	0	583	33,969	
R8	17,660	9,256	2,640	1,661	27	8	31,252	8	43	51	52,938	552	308	228	536	318	0	1,406	85,647	
R9	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
R10	44,377	33,307	16,536	7,786	86	25	102,117	12	60	72	172,985	4,266	1,187	956	2,143	1,887	0	8,296	283,470	
合計	868,855	537,148	245,603	95,446	3,119	1,024	1,751,195	3,007	1,359	4,366	2,966,525	62,474	20,111	24,438	44,549	22,742	0	129,765	4,851,851	

氾濫 ブロック	被害額										流量規模:1/70			河道		現況	施設	現ダム		
	水系名:木曾川					河川名:木曾川					公共土木 施設等 被害額	営業停止 損失	家庭における応急対策費用		事業所に おける応 急対策費用				その他 の間接 被害	
	一般資産被害額		農漁家資産		小計	水稲	畑作物	小計	清掃労働 対価	代替 活動等			小計							
家屋	家庭用品	事業所資産 償却	在庫	農漁家資産 償却							在庫									
L1	52,906	32,805	14,651	4,810	201	65	105,438	543	27	570	178,612	3,901	1,346	2,270	3,616	1,105	0	8,622	293,242	
L2	143,645	86,529	38,200	13,531	905	319	283,129	1,333	97	1,430	479,621	8,972	3,265	5,072	8,337	2,618	0	19,927	784,107	
L3	308,544	192,025	80,612	32,561	1,475															

様式 - 3	被害額										水系名:木曾川			河川名:木曾川			流量規模:1/200			河道	現況	施設	新丸完成	
	氾濫ブロック	一般資産被害額						農作物被害額			公共土木施設等被害額	営業停止損失	家庭における応急対策費用			事業所における応急対策費用	その他の間接被害	小計	合計					備考
		家屋	家庭用品	事業所資産		農漁家資産		小計	水稲	畑作物			小計	清掃労働対価	代替活動等									
L1	66,929	40,545	18,387	6,242	263	85	132,451	701	34	735	224,373	4,825	1,620	2,714	4,334	1,316	0	10,475	368,034					
L2	197,085	120,126	52,927	19,430	1,092	391	391,051	1,485	109	1,594	662,442	11,390	4,373	6,259	10,632	3,690	0	25,712	1,080,799					
L3	388,889	240,966	103,568	42,481	1,774	627	778,305	1,917	291	2,208	1,318,450	21,952	8,566	11,307	19,873	8,068	0	49,893	2,148,856					
L4	32,638	20,598	4,415	2,240	19	6	59,916	0	39	39	101,496	914	705	577	1,282	695	0	2,891	164,342					
L5	31,411	17,950	4,852	2,271	25	8	56,517	63	9	72	95,741	1,581	705	960	1,665	698	0	3,944	156,274					
L6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
L7	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
R1	109,970	64,274	13,247	5,789	566	159	194,005	286	15	301	328,644	3,780	2,234	1,442	3,676	1,275	0	8,731	531,681					
R2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
R3	138,568	88,763	34,003	14,331	404	126	276,195	564	433	997	467,874	7,617	3,050	3,326	6,376	3,367	0	17,360	762,426					
R4	188,901	128,639	54,679	22,155	472	157	395,003	729	600	1,329	669,134	12,075	4,388	5,103	9,491	4,900	0	26,466	1,091,932					
R5	105,613	73,968	54,212	17,825	178	60	251,856	285	286	571	426,642	14,462	3,059	4,455	7,514	5,018	0	26,994	706,063					
R6	350,335	273,752	177,578	61,740	645	223	864,273	892	791	1,683	1,464,081	43,865	10,646	12,847	23,493	17,738	0	85,096	2,415,133					
R7	8,417	2,874	708	387	2	0	12,388	0	15	15	20,986	262	97	61	158	165	0	585	33,974					
R8	17,474	9,158	2,624	1,645	26	8	30,935	7	42	49	52,403	546	306	226	532	314	0	1,392	84,779					
R9	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
R10	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
合計	893,675	545,265	251,166	95,429	3,266	1,081	1,789,882	3,197	1,329	4,526	3,032,060	63,164	20,503	25,583	46,086	22,834	0	132,084	4,958,552					

様式 - 3	被害額										水系名:木曾川			河川名:木曾川			流量規模:1/100			河道	現況	施設	新丸完成	
	氾濫ブロック	一般資産被害額						農作物被害額			公共土木施設等被害額	営業停止損失	家庭における応急対策費用			事業所における応急対策費用	その他の間接被害	小計	合計					備考
		家屋	家庭用品	事業所資産		農漁家資産		小計	水稲	畑作物			小計	清掃労働対価	代替活動等									
L1	50,512	30,356	13,450	4,478	189	60	99,045	530	26	556	167,783	3,750	1,279	2,188	3,467	1,041	0	8,258	275,642					
L2	142,292	85,214	38,235	13,632	862	304	280,539	1,328	88	1,416	475,233	8,858	3,206	4,979	8,185	2,577	0	19,820	776,808					
L3	300,955	183,898	78,919	31,144	1,402	492	596,810	1,630	243	1,873	1,010,996	17,175	6,551	9,161	15,712	6,078	0	38,965	1,648,644					
L4	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
L5	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
L6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
L7	1,438	823	288	151	3	1	2,704	3	14	17	4,582	88	28	22	50	33	0	171	7,474					
R1	107,213	63,697	13,184	5,723	557	157	190,531	286	15	301	322,761	3,692	2,200	1,433	3,633	1,267	0	8,592	522,185					
R2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
R3	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
R4	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
R5	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
R6	181,238	134,498	98,795	32,028	316	109	446,984	507	452	959	757,192	25,566	5,448	7,500	12,948	9,030	0	47,544	1,252,679					
R7	8,417	2,874	707	386	2	0	12,386	0	15	15	20,983	258	97	61	158	165	0	581	33,965					
R8	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
R9	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
R10	16,014	11,732	4,722	1,860	35	11	34,374	8	30	38	58,231	1,299	415	410	825	596	0	2,720	95,363					
合計	595,694	367,179	187,203	68,277	2,474	825	1,221,652	2,546	788	3,334	2,069,479	47,177	14,037	17,963	32,000	16,220	0	95,397	3,389,862					

様式 - 3	被害額										水系名:木曾川			河川名:木曾川			流量規模:1/77			河道	現況	施設	新丸完成	
	氾濫ブロック	一般資産被害額						農作物被害額			公共土木施設等被害額	営業停止損失	家庭における応急対策費用			事業所における応急対策費用	その他の間接被害	小計	合計					備考
		家屋	家庭用品	事業所資産		農漁家資産		小計	水稲	畑作物			小計	清掃労働対価	代替活動等									
L1	44,955	26,563	11,725	3,935	167	53	87,398	485	24	509	148,050	3,371	1,137	1,956	3,093	938	0	7,402	243,359					
L2	124,074	72,764	32,472	11,576	789	275	241,950	1,243	81	1,324	409,862	7,588	2,756	4,392	7,148	2,103	0	16,839	669,975					
L3	268,631	162,168	69,638	27,086	1,273	444	529,240	1,481	227	1,708	896,532	15,515	5,861	8,408	14,269	5,390	0	35,174	1,462,654					
L4	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
L5	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
L6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
L7	1,253	711	247	134	3	1	2,349	3	13	16	3,979	76	25	20	45	30	0	151	6,495					
R1	103,949	62,911	13,062	5,636	549	154	186,261	286	15	301	315,527	3,599	2,160	1,423	3,583	1,257	0	8,439	510,528					
R2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
R3	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
R4	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
R5	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
R6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
R7	8,273	2,861	706	385	2	0	12,227	0	15	15	20,712	256	96	61	157	165	0	578	33,532					
R8	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
R9	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
R10	7,194	5,897	2,233	699	15	5	16,043	7	17	24	27,177	684	214	225	439	351	0	1,474	44,718					
合計	385,445	217,845	82,709	33,062	2,055	680	721,796	1,961	312	2,273	1,222,725	20,150	8,070	9,933	18,003	6,772	0	44,925	1,991,719					

様式 - 3	被害額										水系名:木曾川			河川名:木曾川			流量規模:1/70			河道	現況	施設	新丸完成	
	氾濫ブロック	一般資産被害額						農作物被害額			公共土木施設等被害額	営業停止損失	家庭における応急対策費用			事業所における応急対策費用	その他の間接被害	小計	合計					備考
		家屋	家庭用品	事業所資産		農漁家資産		小計	水稲	畑作物			小計	清掃労働対価	代替活動等									
L1	43,471	25,485	11,397	3,830	160	51	84,394	475	24	499	142,961	3,268	1,095	1,884	2,979	908	0	7,155	235,009					
L2	115,254	68,360	30,194	10,738	761	265	225,572	1,199	78	1,277	382,118	7,045	2,570											

様式 - 4 年平均被害軽減期待額 水系名: 木曽川 河川名: 木曽川 対象: 全体事業評価

流量規模	超過確率	被害額(百万円)			区間平均被害額(百万円)④	区間確率⑤	年平均被害額(百万円)④×⑤	年平均被害額の累計=年平均被害軽減期待額(百万円)	備考
		事業を実施しない場合①	事業を実施した場合②	軽減額③=①-②					
1/3	0.333	0	0	0	34,458	0.133	4,594	4,594	
1/5	0.200	68,915	0	68,915	310,585	0.100	31,058	35,653	
1/10	0.100	552,254	0	552,254	683,694	0.050	34,185	69,837	
1/20	0.050	815,133	0	815,133	1,606,239	0.025	40,156	109,993	
1/40	0.025	2,397,345	0	2,397,345	3,608,699	0.011	38,665	148,658	
1/70	0.014	4,820,052	0	4,820,052	4,887,728	0.001	6,348	155,006	
1/77	0.013	4,955,404	0	4,955,404	5,296,383	0.003	15,820	170,826	
1/100	0.010	5,664,038	26,677	5,637,361	4,665,141	0.005	23,326	194,152	
1/200	0.005	7,288,219	3,595,298	3,692,921				194,152	百万円

様式 - 4 年平均被害軽減期待額 水系名: 木曽川 河川名: 木曽川 対象: 全体事業評価

流量規模	超過確率	被害額(百万円)			区間平均被害額(百万円)④	区間確率⑤	年平均被害額(百万円)④×⑤	年平均被害額の累計=年平均被害軽減期待額(百万円)	備考
		事業を実施しない場合①	事業を実施した場合②	軽減額③=①-②					
1/3	0.333	0	0	0	34,458	0.133	4,594	4,594	
1/5	0.200	68,915	0	68,915	308,131	0.100	30,813	35,407	
1/10	0.100	547,346	0	547,346	673,509	0.050	33,675	69,083	
1/20	0.050	799,671	0	799,671	1,375,225	0.025	34,381	103,463	
1/40	0.025	1,950,779	0	1,950,779	2,118,767	0.011	22,701	126,165	
1/70	0.014	2,286,755	0	2,286,755	2,335,773	0.001	3,033	129,198	
1/77	0.013	2,384,790	0	2,384,790	2,458,520	0.003	7,344	136,542	
1/100	0.010	2,558,926	26,677	2,532,249	2,008,783	0.005	10,044	146,586	
1/200	0.005	5,080,615	3,595,298	1,485,317				146,586	百万円

様式 - 4 年平均被害軽減期待額 水系名: 木曽川 河川名: 木曽川 対象: 全体事業評価

流量規模	超過確率	被害額(百万円)			区間平均被害額(百万円)④	区間確率⑤	年平均被害額(百万円)④×⑤	年平均被害額の累計=年平均被害軽減期待額(百万円)	備考
		事業を実施しない場合①	事業を実施した場合②	軽減額③=①-②					
1/3	0.333	0	0	0	0	0.133	0	0	
1/5	0.200	0	0	0	0	0.100	0	0	
1/10	0.100	0	0	0	0	0.050	0	0	
1/20	0.050	0	0	0	54,130	0.025	1,353	1,353	
1/40	0.025	108,259	0	108,259	1,877,652	0.011	20,118	21,471	
1/70	0.014	3,647,044	0	3,647,044	3,696,013	0.001	4,800	26,271	
1/77	0.013	3,744,981	0	3,744,981	4,135,287	0.003	12,352	38,623	
1/100	0.010	4,552,269	26,677	4,525,592	3,856,622	0.005	19,283	57,906	
1/200	0.005	6,782,950	3,595,298	3,187,652				57,906	百万円

	河道	施設	被害軽減額	備考
①	着手	未完成	194,152	
②	着手	完成	146,586	
③	整備	未完成	57,906	
按分	④=①×②/(②+③)		139,174	河川分
計算式	⑤=①-④		54,978	施設分

様式 - 4 年平均被害軽減期待額 水系名: 木曽川 河川名: 木曽川 対象: 残事業評価

流量規模	超過確率	被害額(百万円)			区間平均被害額(百万円)④	区間確率⑤	年平均被害額(百万円)④×⑤	年平均被害額の累計=年平均被害軽減期待額(百万円)	備考
		事業を実施しない場合①	事業を実施した場合②	軽減額③=①-②					
1/3	0.333	0	0	0	7,242	0.133	966	966	
1/5	0.200	14,483	0	14,483	196,026	0.100	19,603	20,568	
1/10	0.100	377,569	0	377,569	487,906	0.050	24,395	44,963	
1/20	0.050	598,242	0	598,242	1,943,396	0.025	48,585	93,548	
1/40	0.025	3,288,549	0	3,288,549	4,039,384	0.011	43,279	136,827	
1/70	0.014	4,790,219	0	4,790,219	4,821,035	0.001	6,261	143,088	
1/77	0.013	4,851,851	0	4,851,851	5,202,291	0.003	15,539	158,628	
1/100	0.010	5,579,407	26,677	5,552,730	4,612,747	0.005	23,064	181,692	
1/200	0.005	7,268,062	3,595,298	3,672,764				181,692	百万円

様式 - 4 年平均被害軽減期待額 水系名: 木曽川 河川名: 木曽川 対象: 残事業評価

流量規模	超過確率	被害額(百万円)			区間平均被害額(百万円)④	区間確率⑤	年平均被害額(百万円)④×⑤	年平均被害額の累計=年平均被害軽減期待額(百万円)	備考
		事業を実施しない場合①	事業を実施した場合②	軽減額③=①-②					
1/3	0.333	0	0	0	7,242	0.133	966	966	
1/5	0.200	14,483	0	14,483	193,392	0.100	19,339	20,305	
1/10	0.100	372,301	0	372,301	410,747	0.050	20,537	40,842	
1/20	0.050	449,193	0	449,193	1,036,580	0.025	25,914	66,757	
1/40	0.025	1,623,966	0	1,623,966	1,786,643	0.011	19,143	85,899	
1/70	0.014	1,949,319	0	1,949,319	1,970,519	0.001	2,559	88,458	
1/77	0.013	1,991,719	0	1,991,719	2,677,452	0.003	7,998	96,456	
1/100	0.010	3,389,862	26,677	3,363,185	2,363,220	0.005	11,816	108,272	
1/200	0.005	4,958,552	3,595,298	1,363,254				108,272	百万円

様式 - 4 年平均被害軽減期待額 水系名: 木曽川 河川名: 木曽川 対象: 残事業評価

流量規模	超過確率	被害額(百万円)			区間平均被害額(百万円)④	区間確率⑤	年平均被害額(百万円)④×⑤	年平均被害額の累計=年平均被害軽減期待額(百万円)	備考
		事業を実施しない場合①	事業を実施した場合②	軽減額③=①-②					
1/3	0.333	0	0	0	0	0.133	0	0	
1/5	0.200	0	0	0	0	0.100	0	0	
1/10	0.100	0	0	0	0	0.050	0	0	
1/20	0.050	0	0	0	54,130	0.025	1,353	1,353	
1/40	0.025	108,259	0	108,259	1,877,652	0.011	20,118	21,471	
1/70	0.014	3,647,044	0	3,647,044	3,696,013	0.001	4,800	26,271	
1/77	0.013	3,744,981	0	3,744,981	4,135,287	0.003	12,352	38,623	
1/100	0.010	4,552,269	26,677	4,525,592	3,856,622	0.005	19,283	57,906	
1/200	0.005	6,782,950	3,595,298	3,187,652				57,906	百万円

	河道	施設	被害軽減額	備考
①	現況	未完成	181,692	
②	現況	新丸	108,272	
③	整備	未完成	57,906	
按分	④=①×②/(②+③)		118,380	河川分
計算式	⑤=①-④		63,312	施設分

年次	t	便 益			費 用				費用便益比 B/C	純現在価値 B-C					
		便 益	①	②	建設費		維持管理費				③	④			
			現在価値	残存価値	①+②	費用	現在価値	費用			現在価値	費用			
整備期間	H20	-3	0	0				737	829	0	0	737	829		
	H21	-2	4,639	5,018				2,984	3,228	10	11	2,994	3,238		
	H22	-1	9,278	9,649				3,466	3,605	20	20	3,486	3,625		
	H23	0	13,917	13,917				2,377	2,377	29	29	2,407	2,407		
	H24	1	18,556	17,843				1,246	1,198	317	304	1,563	1,503		
	H25	2	23,196	21,446				1,650	1,526	318	294	1,968	1,819		
	H26	3	27,835	24,745				2,285	2,031	179	159	2,464	2,190		
	H27	4	32,474	27,759				2,133	1,823	41	35	2,174	1,858		
	H28	5	37,113	30,504				1,683	1,383	42	35	1,725	1,418		
	H29	6	41,752	32,997				2,304	1,821	43	34	2,347	1,855		
	H30	7	46,391	35,253				2,304	1,751	45	34	2,349	1,785		
	H31	8	51,030	37,287				2,304	1,683	47	34	2,351	1,718		
	H32	9	55,669	39,113				2,304	1,619	49	34	2,353	1,653		
	H33	10	60,309	40,742				2,304	1,556	50	34	2,354	1,591		
	H34	11	64,948	42,189				2,304	1,497	52	34	2,356	1,530		
	H35	12	69,587	43,464				2,304	1,439	54	34	2,358	1,473		
	H36	13	74,226	44,578				2,304	1,384	56	33	2,360	1,417		
	H37	14	78,865	45,543				2,304	1,330	57	33	2,361	1,364		
	H38	15	83,504	46,367				2,304	1,279	59	33	2,363	1,312		
	H39	16	88,143	47,060				2,304	1,230	61	33	2,365	1,263		
	H40	17	92,782	47,632				2,304	1,183	153	78	2,457	1,261		
	H41	18	97,422	48,090				2,304	1,137	214	106	2,518	1,243		
	H42	19	102,061	48,442				2,304	1,094	366	174	2,670	1,267		
	H43	20	106,700	48,696				2,304	1,051	68	31	2,372	1,082		
	H44	21	111,339	48,859				2,304	1,011	70	31	2,374	1,042		
	H45	22	115,978	48,938				2,304	972	71	30	2,375	1,002		
	H46	23	120,617	48,938				2,304	935	73	30	2,377	964		
	H47	24	125,256	48,865				2,304	899	75	29	2,379	928		
	H48	25	129,895	48,726				2,304	864	77	29	2,381	893		
H49	26	134,534	48,525				2,304	831	78	28	2,382	859			
評価期間	H50	27	139,174	48,268					122	42	122	42			
	H51	28	139,174	46,411					122	41	122	41			
	H52	29	139,174	44,626					122	39	122	39			
	H53	30	139,174	42,910					122	37	122	37			
	H54	31	139,174	41,259					122	36	122	36			
	H55	32	139,174	39,673					122	35	122	35			
	H56	33	139,174	38,147					122	33	122	33			
	H57	34	139,174	36,679					122	32	122	32			
	H58	35	139,174	35,269					122	31	122	31			
	H59	36	139,174	33,912					122	30	122	30			
	H60	37	139,174	32,608					122	28	122	28			
	H61	38	139,174	31,354					122	27	122	27			
	H62	39	139,174	30,148					122	26	122	26			
	H63	40	139,174	28,988					122	25	122	25			
	H64	41	139,174	27,873					122	24	122	24			
	H65	42	139,174	26,801					122	23	122	23			
	H66	43	139,174	25,771					122	23	122	23			
	H67	44	139,174	24,779					122	22	122	22			
	H68	45	139,174	23,826					122	21	122	21			
	H69	46	139,174	22,910					122	20	122	20			
	H70	47	139,174	22,029					122	19	122	19			
	H71	48	139,174	21,181					122	18	122	18			
	H72	49	139,174	20,367					122	18	122	18			
	H73	50	139,174	19,583					122	17	122	17			
	H74	51	139,174	18,830					122	16	122	16			
	H75	52	139,174	18,106					122	16	122	16			
	H76	53	139,174	17,410					122	15	122	15			
	H77	54	139,174	16,740					122	15	122	15			
	H78	55	139,174	16,096					122	14	122	14			
	H79	56	139,174	15,477					122	14	122	14			
	H80	57	139,174	14,882					122	13	122	13			
	H81	58	139,174	14,309					122	12	122	12			
	H82	59	139,174	13,759					122	12	122	12			
H83	60	139,174	13,230					122	12	122	12				
H84	61	139,174	12,721					122	11	122	11				
H85	62	139,174	12,232					122	11	122	11				
H86	63	139,174	11,761					122	10	122	10				
H87	64	139,174	11,309					122	10	122	10				
H88	65	139,174	10,874					122	9	122	9				
H89	66	139,174	10,456					122	9	122	9				
H90	67	139,174	10,054					122	9	122	9				
H91	68	139,174	9,667					122	8	122	8				
H92	69	139,174	9,295					122	8	122	8				
H93	70	139,174	8,938					122	8	122	8				
H94	71	139,174	8,594					122	8	122	8				
H95	72	139,174	8,263					122	7	122	7				
H96	73	139,174	7,946					122	7	122	7				
H97	74	139,174	7,640					122	7	122	7				
H98	75	139,174	7,346					122	6	122	6				
H99	76	139,174	7,064					122	6	122	6				
合計			8,976,696	2,169,557	912	2,170,469	66,943	44,566	8,852	2,766	75,794	47,332	45.9	2,123.137	

年次	t	便 益			費 用				費用便益比 B/C	純現在価値 B-C				
		便 益	①		建設費		維持管理費							
			現在価値	残存価値	費用	現在価値	費用	現在価値						
				①+②			③	④						
整備期間	H20	-3	0	0			737	829	0	0	737	829		
	H21	-2	4,639	5,018			2,984	3,228	10	11	2,994	3,238		
	H22	-1	9,278	9,649			3,466	3,605	20	20	3,486	3,625		
	H23	0	13,917	13,917			2,377	2,377	29	29	2,407	2,407		
	H24	1	18,556	17,843			1,371	1,318	317	304	1,687	1,622		
	H25	2	23,196	21,446			1,815	1,678	318	294	2,133	1,972		
	H26	3	27,835	24,745			2,514	2,234	179	159	2,692	2,394		
	H27	4	32,474	27,759			2,346	2,006	41	35	2,387	2,040		
	H28	5	37,113	30,504			1,851	1,522	42	35	1,894	1,556		
	H29	6	41,752	32,997			2,534	2,003	43	34	2,578	2,037		
	H30	7	46,391	35,253			2,534	1,926	45	34	2,579	1,960		
	H31	8	51,030	37,287			2,534	1,852	47	34	2,581	1,886		
	H32	9	55,669	39,113			2,534	1,781	49	34	2,583	1,815		
	H33	10	60,309	40,742			2,534	1,712	50	34	2,585	1,746		
	H34	11	64,948	42,189			2,534	1,646	52	34	2,586	1,680		
	H35	12	69,587	43,464			2,534	1,583	54	34	2,588	1,617		
	H36	13	74,226	44,578			2,534	1,522	56	33	2,590	1,555		
	H37	14	78,865	45,543			2,534	1,463	57	33	2,592	1,497		
	H38	15	83,504	46,367			2,534	1,407	59	33	2,593	1,440		
	H39	16	88,143	47,060			2,534	1,353	61	33	2,595	1,386		
	H40	17	92,782	47,632			2,534	1,301	153	78	2,687	1,379		
	H41	18	97,422	48,090			2,534	1,251	214	106	2,749	1,357		
	H42	19	102,061	48,442			2,534	1,203	366	174	2,900	1,377		
	H43	20	106,700	48,896			2,534	1,157	68	31	2,602	1,188		
	H44	21	111,339	48,859			2,534	1,112	70	31	2,604	1,143		
	H45	22	115,978	48,938			2,534	1,069	71	30	2,606	1,099		
H46	23	120,617	48,938			2,534	1,028	73	30	2,607	1,058			
H47	24	125,256	48,865			2,534	989	75	29	2,609	1,018			
H48	25	129,895	48,726			2,534	951	77	29	2,611	979			
H49	26	134,534	48,525			2,534	914	78	28	2,613	942			
評価期間	H50	27	139,174	48,268					122	42	122	42		
	H51	28	139,174	46,411					122	41	122	41		
	H52	29	139,174	44,626					122	39	122	39		
	H53	30	139,174	42,910					122	37	122	37		
	H54	31	139,174	41,259					122	36	122	36		
	H55	32	139,174	39,673					122	35	122	35		
	H56	33	139,174	38,147					122	33	122	33		
	H57	34	139,174	36,679					122	32	122	32		
	H58	35	139,174	35,269					122	31	122	31		
	H59	36	139,174	33,912					122	30	122	30		
	H60	37	139,174	32,608					122	28	122	28		
	H61	38	139,174	31,354					122	27	122	27		
	H62	39	139,174	30,148					122	26	122	26		
	H63	40	139,174	28,988					122	25	122	25		
	H64	41	139,174	27,873					122	24	122	24		
	H65	42	139,174	26,801					122	23	122	23		
	H66	43	139,174	25,771					122	23	122	23		
	H67	44	139,174	24,779					122	22	122	22		
	H68	45	139,174	23,826					122	21	122	21		
	H69	46	139,174	22,910					122	20	122	20		
	H70	47	139,174	22,029					122	19	122	19		
	H71	48	139,174	21,181					122	18	122	18		
	H72	49	139,174	20,367					122	18	122	18		
	H73	50	139,174	19,583					122	17	122	17		
	H74	51	139,174	18,830					122	16	122	16		
	H75	52	139,174	18,106					122	16	122	16		
	H76	53	139,174	17,410					122	15	122	15		
	H77	54	139,174	16,740					122	15	122	15		
	H78	55	139,174	16,096					122	14	122	14		
	H79	56	139,174	15,477					122	14	122	14		
H80	57	139,174	14,882					122	13	122	13			
H81	58	139,174	14,309					122	12	122	12			
H82	59	139,174	13,759					122	12	122	12			
H83	60	139,174	13,230					122	12	122	12			
H84	61	139,174	12,721					122	11	122	11			
H85	62	139,174	12,232					122	11	122	11			
H86	63	139,174	11,761					122	10	122	10			
H87	64	139,174	11,309					122	10	122	10			
H88	65	139,174	10,874					122	9	122	9			
H89	66	139,174	10,456					122	9	122	9			
H90	67	139,174	10,054					122	9	122	9			
H91	68	139,174	9,667					122	8	122	8			
H92	69	139,174	9,295					122	8	122	8			
H93	70	139,174	8,938					122	8	122	8			
H94	71	139,174	8,594					122	8	122	8			
H95	72	139,174	8,263					122	7	122	7			
H96	73	139,174	7,946					122	7	122	7			
H97	74	139,174	7,640					122	7	122	7			
H98	75	139,174	7,346					122	6	122	6			
H99	76	139,174	7,064					122	6	122	6			
合計			8,976,696	2,169,557	985	2,170,542	72,681	48,019	8,852	2,766	81,532	50,785	42.7	2,119,757

年次	t	便 益			費 用				費用便益比 B/C	純現在価値 B-C					
		便 益	①	②	建設費		維持管理費				③	④			
			現在価値	残存価値	①+②	費 用	現在価値	費 用			現在価値				
整備期間	H20	-3	0	0				737	829	0	0	737	829		
	H21	-2	4,639	5,018				2,984	3,228	10	11	2,994	3,238		
	H22	-1	9,278	9,649				3,466	3,605	20	20	3,486	3,625		
	H23	0	13,917	13,917				2,377	2,377	29	29	2,407	2,407		
	H24	1	18,556	17,843				1,121	1,078	317	304	1,438	1,383		
	H25	2	23,196	21,446				1,485	1,373	318	294	1,803	1,667		
	H26	3	27,835	24,745				2,057	1,828	179	159	2,235	1,987		
	H27	4	32,474	27,759				1,920	1,641	41	35	1,960	1,676		
	H28	5	37,113	30,504				1,515	1,245	42	35	1,557	1,280		
	H29	6	41,752	32,997				2,073	1,639	43	34	2,117	1,673		
	H30	7	46,391	35,253				2,073	1,576	45	34	2,119	1,610		
	H31	8	51,030	37,287				2,073	1,515	47	34	2,120	1,549		
	H32	9	55,669	39,113				2,073	1,457	49	34	2,122	1,491		
	H33	10	60,309	40,742				2,073	1,401	50	34	2,124	1,435		
	H34	11	64,948	42,189				2,073	1,347	52	34	2,126	1,381		
	H35	12	69,587	43,464				2,073	1,295	54	34	2,127	1,329		
	H36	13	74,226	44,578				2,073	1,245	56	33	2,129	1,279		
	H37	14	78,865	45,543				2,073	1,197	57	33	2,131	1,231		
	H38	15	83,504	46,367				2,073	1,151	59	33	2,133	1,184		
	H39	16	88,143	47,060				2,073	1,107	61	33	2,134	1,140		
	H40	17	92,782	47,632				2,073	1,064	153	78	2,226	1,143		
	H41	18	97,422	48,090				2,073	1,024	214	106	2,288	1,129		
	H42	19	102,061	48,442				2,073	984	366	174	2,440	1,158		
	H43	20	106,700	48,696				2,073	946	68	31	2,141	977		
	H44	21	111,339	48,859				2,073	910	70	31	2,143	940		
	H45	22	115,978	48,938				2,073	875	71	30	2,145	905		
H46	23	120,617	48,938				2,073	841	73	30	2,147	871			
H47	24	125,256	48,865				2,073	809	75	29	2,148	838			
H48	25	129,895	48,726				2,073	778	77	29	2,150	807			
H49	26	134,534	48,525				2,073	748	78	28	2,152	776			
評価期間	H50	27	139,174	48,268						122	42	122	42		
	H51	28	139,174	46,411						122	41	122	41		
	H52	29	139,174	44,626						122	39	122	39		
	H53	30	139,174	42,910						122	37	122	37		
	H54	31	139,174	41,259						122	36	122	36		
	H55	32	139,174	39,673						122	35	122	35		
	H56	33	139,174	38,147						122	33	122	33		
	H57	34	139,174	36,679						122	32	122	32		
	H58	35	139,174	35,269						122	31	122	31		
	H59	36	139,174	33,912						122	30	122	30		
	H60	37	139,174	32,608						122	28	122	28		
	H61	38	139,174	31,354						122	27	122	27		
	H62	39	139,174	30,148						122	26	122	26		
	H63	40	139,174	28,988						122	25	122	25		
	H64	41	139,174	27,873						122	24	122	24		
	H65	42	139,174	26,801						122	23	122	23		
	H66	43	139,174	25,771						122	23	122	23		
	H67	44	139,174	24,779						122	22	122	22		
	H68	45	139,174	23,826						122	21	122	21		
	H69	46	139,174	22,910						122	20	122	20		
	H70	47	139,174	22,029						122	19	122	19		
	H71	48	139,174	21,181						122	18	122	18		
	H72	49	139,174	20,367						122	18	122	18		
	H73	50	139,174	19,583						122	17	122	17		
	H74	51	139,174	18,830						122	16	122	16		
	H75	52	139,174	18,106						122	16	122	16		
	H76	53	139,174	17,410						122	15	122	15		
	H77	54	139,174	16,740						122	15	122	15		
	H78	55	139,174	16,096						122	14	122	14		
	H79	56	139,174	15,477						122	14	122	14		
	H80	57	139,174	14,882						122	13	122	13		
	H81	58	139,174	14,309						122	12	122	12		
	H82	59	139,174	13,759						122	12	122	12		
	H83	60	139,174	13,230						122	12	122	12		
H84	61	139,174	12,721						122	11	122	11			
H85	62	139,174	12,232						122	11	122	11			
H86	63	139,174	11,761						122	10	122	10			
H87	64	139,174	11,309						122	10	122	10			
H88	65	139,174	10,874						122	9	122	9			
H89	66	139,174	10,456						122	9	122	9			
H90	67	139,174	10,054						122	9	122	9			
H91	68	139,174	9,667						122	8	122	8			
H92	69	139,174	9,295						122	8	122	8			
H93	70	139,174	8,938						122	8	122	8			
H94	71	139,174	8,594						122	8	122	8			
H95	72	139,174	8,263						122	7	122	7			
H96	73	139,174	7,946						122	7	122	7			
H97	74	139,174	7,640						122	7	122	7			
H98	75	139,174	7,346						122	6	122	6			
H99	76	139,174	7,064						122	6	122	6			
合計			8,976,696	2,169,557	838	2,170,395	61,205	41,114	8,852	2,766	70,057	43,879	49.5	2,126,516	

年次	t	便 益				費 用						費用便益比 B/C	純現在価値 B-C	
		便 益	①		①+②	建設費		維持管理費		③				
			現在価値	残存価値		費 用	現在価値	費 用	現在価値	費 用	現在価値			
整備期間	H20	-3	0	0		737	829	0	0	737	829			
	H21	-2	4,217	4,562		2,984	3,228	10	11	2,994	3,238			
	H22	-1	8,435	8,772		3,466	3,605	20	20	3,486	3,625			
	H23	0	12,652	12,652		2,377	2,377	29	29	2,407	2,407			
	H24	1	16,870	16,221		1,117	1,074	317	304	1,434	1,379			
	H25	2	21,087	19,496		1,438	1,329	318	294	1,755	1,623			
	H26	3	25,304	22,495		1,917	1,704	179	159	2,096	1,863			
	H27	4	29,522	25,235		1,960	1,675	41	35	2,000	1,710			
	H28	5	33,739	27,731		1,695	1,393	42	35	1,737	1,428			
	H29	6	37,956	29,998		1,744	1,379	43	34	1,788	1,413			
	H30	7	42,174	32,049		2,066	1,570	45	34	2,111	1,604			
	H31	8	46,391	33,898		2,066	1,509	47	34	2,113	1,544			
	H32	9	50,609	35,557		2,066	1,451	49	34	2,114	1,485			
	H33	10	54,826	37,038		2,066	1,395	50	34	2,116	1,430			
	H34	11	59,043	38,353		2,066	1,342	52	34	2,118	1,376			
	H35	12	63,261	39,512		2,066	1,290	54	34	2,120	1,324			
	H36	13	67,478	40,526		2,066	1,241	56	33	2,121	1,274			
	H37	14	71,695	41,402		2,066	1,193	57	33	2,123	1,226			
	H38	15	75,913	42,152		2,066	1,147	59	33	2,125	1,180			
	H39	16	80,130	42,782		2,066	1,103	61	33	2,126	1,135			
	H40	17	84,348	43,302		2,066	1,060	153	78	2,218	1,139			
	H41	18	88,565	43,718		2,066	1,020	214	106	2,280	1,125			
	H42	19	92,782	44,038		2,066	980	366	174	2,432	1,154			
	H43	20	97,000	44,269		2,066	943	68	31	2,133	974			
	H44	21	101,217	44,417		2,066	906	70	31	2,135	937			
H45	22	105,435	44,489		2,066	872	71	30	2,137	902				
H46	23	109,652	44,489		2,066	838	73	30	2,139	868				
H47	24	113,869	44,423		2,066	806	75	29	2,140	835				
H48	25	118,087	44,296		2,066	775	77	29	2,142	804				
H49	26	122,304	44,114		2,066	745	78	28	2,144	773				
H50	27	126,521	43,880		2,066	716	122	42	2,187	759				
H51	28	130,739	43,598		2,066	689	122	41	2,187	729				
H52	29	134,956	43,274		2,066	662	122	39	2,187	701				
評価期間	H53	30	139,174	42,910				122	37	122	37			
	H54	31	139,174	41,259				122	36	122	36			
	H55	32	139,174	39,673				122	35	122	35			
	H56	33	139,174	38,147				122	33	122	33			
	H57	34	139,174	36,679				122	32	122	32			
	H58	35	139,174	35,269				122	31	122	31			
	H59	36	139,174	33,912				122	30	122	30			
	H60	37	139,174	32,608				122	28	122	28			
	H61	38	139,174	31,354				122	27	122	27			
	H62	39	139,174	30,148				122	26	122	26			
	H63	40	139,174	28,988				122	25	122	25			
	H64	41	139,174	27,873				122	24	122	24			
	H65	42	139,174	26,801				122	23	122	23			
	H66	43	139,174	25,771				122	23	122	23			
	H67	44	139,174	24,779				122	22	122	22			
	H68	45	139,174	23,826				122	21	122	21			
	H69	46	139,174	22,910				122	20	122	20			
	H70	47	139,174	22,029				122	19	122	19			
	H71	48	139,174	21,181				122	18	122	18			
	H72	49	139,174	20,367				122	18	122	18			
	H73	50	139,174	19,583				122	17	122	17			
	H74	51	139,174	18,830				122	16	122	16			
	H75	52	139,174	18,106				122	16	122	16			
	H76	53	139,174	17,410				122	15	122	15			
	H77	54	139,174	16,740				122	15	122	15			
	H78	55	139,174	16,096				122	14	122	14			
	H79	56	139,174	15,477				122	14	122	14			
	H80	57	139,174	14,882				122	13	122	13			
	H81	58	139,174	14,309				122	12	122	12			
	H82	59	139,174	13,759				122	12	122	12			
	H83	60	139,174	13,230				122	12	122	12			
	H84	61	139,174	12,721				122	11	122	11			
	H85	62	139,174	12,232				122	11	122	11			
	H86	63	139,174	11,761				122	10	122	10			
	H87	64	139,174	11,309				122	10	122	10			
	H88	65	139,174	10,874				122	9	122	9			
	H89	66	139,174	10,456				122	9	122	9			
	H90	67	139,174	10,054				122	9	122	9			
	H91	68	139,174	9,667				122	8	122	8			
	H92	69	139,174	9,295				122	8	122	8			
	H93	70	139,174	8,938				122	8	122	8			
	H94	71	139,174	8,594				122	8	122	8			
	H95	72	139,174	8,263				122	7	122	7			
	H96	73	139,174	7,946				122	7	122	7			
	H97	74	139,174	7,640				122	7	122	7			
	H98	75	139,174	7,346				122	6	122	6			
	H99	76	139,174	7,064				122	6	122	6			
	H100	77	139,174	6,792				122	6	122	6			
H101	78	139,174	6,531				122	6	122	6				
H102	79	139,174	6,279				122	5	122	5				
合計			9,185,456	2,081,407	811	2,082,218	66,943	42,846	9,216	2,783	76,159	45,629	45.6	2,036,589

年次	t	便 益				費 用				費用便益比 B/C	純現在価値 B-C			
		便 益	①		②	建設費		維持管理費				③	④	
			現在価値	残存価値		費用	現在価値	費用	現在価値					
整備期間	H20	-3	0	0		737	829	0	0	737	829			
	H21	-2	5,155	5,575		2,984	3,228	10	11	2,994	3,238			
	H22	-1	10,309	10,722		3,466	3,605	20	20	3,486	3,625			
	H23	0	15,464	15,464		2,377	2,377	29	29	2,407	2,407			
	H24	1	20,618	19,825		1,461	1,405	317	304	1,778	1,710			
	H25	2	25,773	23,828		2,031	1,878	318	294	2,348	2,171			
	H26	3	30,927	27,494		2,524	2,243	179	159	2,702	2,402			
	H27	4	36,082	30,843		2,176	1,860	41	35	2,217	1,895			
	H28	5	41,237	33,893		2,307	1,897	42	35	2,350	1,931			
	H29	6	46,391	36,664		2,604	2,058	43	34	2,648	2,093			
	H30	7	51,546	39,171		2,604	1,979	45	34	2,650	2,013			
	H31	8	56,700	41,430		2,604	1,903	47	34	2,651	1,937			
	H32	9	61,855	43,458		2,604	1,830	49	34	2,653	1,864			
	H33	10	67,010	45,269		2,604	1,759	50	34	2,655	1,794			
	H34	11	72,164	46,876		2,604	1,692	52	34	2,657	1,726			
	H35	12	77,319	48,293		2,604	1,627	54	34	2,658	1,660			
	H36	13	82,473	49,531		2,604	1,564	56	33	2,660	1,598			
	H37	14	87,628	50,603		2,604	1,504	57	33	2,662	1,537			
	H38	15	92,782	51,519		2,604	1,446	59	33	2,664	1,479			
	H39	16	97,937	52,289		2,604	1,390	61	33	2,665	1,423			
	H40	17	103,092	52,924		2,604	1,337	153	78	2,757	1,415			
	H41	18	108,246	53,433		2,604	1,286	214	106	2,819	1,391			
	H42	19	113,401	53,825		2,604	1,236	366	174	2,971	1,410			
	H43	20	118,555	54,107		2,604	1,189	68	31	2,672	1,220			
H44	21	123,710	54,288		2,604	1,143	70	31	2,674	1,173				
H45	22	128,864	54,375		2,604	1,099	71	30	2,676	1,129				
H46	23	134,019	54,375		2,604	1,057	73	30	2,678	1,086				
評価期間	H47	24	139,174	54,295				75	29	75	29			
	H48	25	139,174	52,206				77	29	77	29			
	H49	26	139,174	50,198				78	28	78	28			
	H50	27	139,174	48,268				122	42	122	42			
	H51	28	139,174	46,411				122	41	122	41			
	H52	29	139,174	44,626				122	39	122	39			
	H53	30	139,174	42,910				122	37	122	37			
	H54	31	139,174	41,259				122	36	122	36			
	H55	32	139,174	39,673				122	35	122	35			
	H56	33	139,174	38,147				122	33	122	33			
	H57	34	139,174	36,679				122	32	122	32			
	H58	35	139,174	35,269				122	31	122	31			
	H59	36	139,174	33,912				122	30	122	30			
	H60	37	139,174	32,608				122	28	122	28			
	H61	38	139,174	31,354				122	27	122	27			
	H62	39	139,174	30,148				122	26	122	26			
	H63	40	139,174	28,988				122	25	122	25			
	H64	41	139,174	27,873				122	24	122	24			
	H65	42	139,174	26,801				122	23	122	23			
	H66	43	139,174	25,771				122	23	122	23			
	H67	44	139,174	24,779				122	22	122	22			
	H68	45	139,174	23,826				122	21	122	21			
	H69	46	139,174	22,910				122	20	122	20			
	H70	47	139,174	22,029				122	19	122	19			
	H71	48	139,174	21,181				122	18	122	18			
	H72	49	139,174	20,367				122	18	122	18			
	H73	50	139,174	19,583				122	17	122	17			
	H74	51	139,174	18,830				122	16	122	16			
	H75	52	139,174	18,106				122	16	122	16			
	H76	53	139,174	17,410				122	15	122	15			
	H77	54	139,174	16,740				122	15	122	15			
	H78	55	139,174	16,096				122	14	122	14			
	H79	56	139,174	15,477				122	14	122	14			
	H80	57	139,174	14,882				122	13	122	13			
H81	58	139,174	14,309				122	12	122	12				
H82	59	139,174	13,759				122	12	122	12				
H83	60	139,174	13,230				122	12	122	12				
H84	61	139,174	12,721				122	11	122	11				
H85	62	139,174	12,232				122	11	122	11				
H86	63	139,174	11,761				122	10	122	10				
H87	64	139,174	11,309				122	10	122	10				
H88	65	139,174	10,874				122	9	122	9				
H89	66	139,174	10,456				122	9	122	9				
H90	67	139,174	10,054				122	9	122	9				
H91	68	139,174	9,667				122	8	122	8				
H92	69	139,174	9,295				122	8	122	8				
H93	70	139,174	8,938				122	8	122	8				
H94	71	139,174	8,594				122	8	122	8				
H95	72	139,174	8,263				122	7	122	7				
H96	73	139,174	7,946				122	7	122	7				
合計			8,767,936	2,263,098	1,026	2,264,124	66,943	46,421	8,487	2,746	75,430	49,167	46.0	2,214,957

年次	t	便 益			費 用				費用便益比 B/C	純現在価値 B-C			
		便 益	①		建設費		維持管理費						
			現在価値	残存価値	費用	現在価値	費用	現在価値					
	H20 -3	0	0		737	829	0	0	737	829			
	H21 -2	5,092	5,507		2,984	3,228	10	11	2,994	3,238			
	H22 -1	10,184	10,591		3,466	3,605	20	20	3,486	3,625			
	H23 0	15,276	15,276		2,377	2,377	29	29	2,407	2,407			
	H24 1	20,368	19,585		1,246	1,198	317	304	1,563	1,503			
	H25 2	25,460	23,539		1,650	1,526	318	294	1,968	1,819			
	H26 3	30,552	27,161		2,285	2,031	179	159	2,464	2,190			
	H27 4	35,644	30,469		2,133	1,823	41	35	2,174	1,858			
	H28 5	40,736	33,482		1,683	1,383	42	35	1,725	1,418			
	H29 6	45,828	36,218		2,304	1,821	43	34	2,347	1,855			
	H30 7	50,920	38,695		2,304	1,751	45	34	2,349	1,785			
	H31 8	56,012	40,927		2,304	1,683	47	34	2,351	1,718			
	H32 9	61,104	42,931		2,304	1,619	49	34	2,353	1,653			
	H33 10	66,196	44,720		2,304	1,556	50	34	2,354	1,591			
	H34 11	71,288	46,307		2,304	1,497	52	34	2,356	1,530			
	H35 12	76,380	47,707		2,304	1,439	54	34	2,358	1,473			
	H36 13	81,472	48,930		2,304	1,384	56	33	2,360	1,417			
	H37 14	86,564	49,988		2,304	1,330	57	33	2,361	1,364			
	H38 15	91,656	50,893		2,304	1,279	59	33	2,363	1,312			
	H39 16	96,748	51,654		2,304	1,230	61	33	2,365	1,263			
	H40 17	101,840	52,282		2,304	1,183	153	78	2,457	1,261			
	H41 18	106,932	52,785		2,304	1,137	214	106	2,518	1,243			
	H42 19	112,024	53,171		2,304	1,094	366	174	2,670	1,267			
	H43 20	117,116	53,450		2,304	1,051	68	31	2,372	1,082			
	H44 21	122,208	53,629		2,304	1,011	70	31	2,374	1,042			
	H45 22	127,300	53,715		2,304	972	71	30	2,375	1,002			
	H46 23	132,392	53,715		2,304	935	73	30	2,377	964			
	H47 24	137,484	53,635		2,304	899	75	29	2,379	928			
	H48 25	142,576	53,483		2,304	864	77	29	2,381	893			
	H49 26	147,668	53,262		2,304	831	78	28	2,382	859			
	H50 27	152,760	52,980				122	42	122	42			
	H51 28	152,760	50,942				122	41	122	41			
	H52 29	152,760	48,983				122	39	122	39			
	H53 30	152,760	47,099				122	37	122	37			
	H54 31	152,760	45,287				122	36	122	36			
	H55 32	152,760	43,545				122	35	122	35			
	H56 33	152,760	41,871				122	33	122	33			
	H57 34	152,760	40,260				122	32	122	32			
	H58 35	152,760	38,712				122	31	122	31			
	H59 36	152,760	37,223				122	30	122	30			
	H60 37	152,760	35,791				122	28	122	28			
	H61 38	152,760	34,415				122	27	122	27			
	H62 39	152,760	33,091				122	26	122	26			
	H63 40	152,760	31,818				122	25	122	25			
	H64 41	152,760	30,594				122	24	122	24			
	H65 42	152,760	29,418				122	23	122	23			
	H66 43	152,760	28,286				122	23	122	23			
	H67 44	152,760	27,198				122	22	122	22			
	H68 45	152,760	26,152				122	21	122	21			
	H69 46	152,760	25,146				122	20	122	20			
	H70 47	152,760	24,179				122	19	122	19			
	H71 48	152,760	23,249				122	18	122	18			
	H72 49	152,760	22,355				122	18	122	18			
	H73 50	152,760	21,495				122	17	122	17			
	H74 51	152,760	20,668				122	16	122	16			
	H75 52	152,760	19,874				122	16	122	16			
	H76 53	152,760	19,109				122	15	122	15			
	H77 54	152,760	18,374				122	15	122	15			
	H78 55	152,760	17,668				122	14	122	14			
	H79 56	152,760	16,988				122	14	122	14			
	H80 57	152,760	16,335				122	13	122	13			
	H81 58	152,760	15,706				122	12	122	12			
	H82 59	152,760	15,102				122	12	122	12			
	H83 60	152,760	14,521				122	12	122	12			
	H84 61	152,760	13,963				122	11	122	11			
	H85 62	152,760	13,426				122	11	122	11			
	H86 63	152,760	12,909				122	10	122	10			
	H87 64	152,760	12,413				122	10	122	10			
	H88 65	152,760	11,936				122	9	122	9			
	H89 66	152,760	11,476				122	9	122	9			
	H90 67	152,760	11,035				122	9	122	9			
	H91 68	152,760	10,611				122	8	122	8			
	H92 69	152,760	10,203				122	8	122	8			
	H93 70	152,760	9,810				122	8	122	8			
	H94 71	152,760	9,433				122	8	122	8			
	H95 72	152,760	9,070				122	7	122	7			
	H96 73	152,760	8,721				122	7	122	7			
	H97 74	152,760	8,386				122	7	122	7			
	H98 75	152,760	8,063				122	6	122	6			
	H99 76	152,760	7,753				122	6	122	6			
合計		9,853,004	2,381,350	912	2,382,262	66,943	44,566	8,852	2,766	75,794	47,332	50.3	2,334,930

百万円

年次	t	便 益			費 用				費用便益比 B/C	純現在価値 B-C					
		便 益	①	②	建設費		維持管理費				③	④			
			現在価値	残存価値	①+②	費用	現在価値	費用			現在価値	費用	現在価値		
整備期間	H20	-3	0	0				737	829	0	0	737	829		
	H21	-2	4,186	4,528				2,984	3,228	10	11	2,994	3,238		
	H22	-1	8,372	8,707				3,466	3,605	20	20	3,486	3,625		
	H23	0	12,558	12,558				2,377	2,377	29	29	2,407	2,407		
	H24	1	16,744	16,100				1,246	1,198	317	304	1,563	1,503		
	H25	2	20,930	19,351				1,650	1,526	318	294	1,968	1,819		
	H26	3	25,116	22,328				2,285	2,031	179	159	2,464	2,190		
	H27	4	29,302	25,048				2,133	1,823	41	35	2,174	1,858		
	H28	5	33,488	27,525				1,683	1,383	42	35	1,725	1,418		
	H29	6	37,674	29,775				2,304	1,821	43	34	2,347	1,855		
	H30	7	41,860	31,810				2,304	1,751	45	34	2,349	1,785		
	H31	8	46,046	33,646				2,304	1,683	47	34	2,351	1,718		
	H32	9	50,232	35,293				2,304	1,619	49	34	2,353	1,653		
	H33	10	54,418	36,763				2,304	1,556	50	34	2,354	1,591		
	H34	11	58,605	38,068				2,304	1,497	52	34	2,356	1,530		
	H35	12	62,791	39,219				2,304	1,439	54	34	2,358	1,473		
	H36	13	66,977	40,224				2,304	1,384	56	33	2,360	1,417		
	H37	14	71,163	41,095				2,304	1,330	57	33	2,361	1,364		
	H38	15	75,349	41,838				2,304	1,279	59	33	2,363	1,312		
	H39	16	79,535	42,464				2,304	1,230	61	33	2,365	1,263		
	H40	17	83,721	42,980				2,304	1,183	153	78	2,457	1,261		
	H41	18	87,907	43,393				2,304	1,137	214	106	2,518	1,243		
	H42	19	92,093	43,711				2,304	1,094	366	174	2,670	1,267		
	H43	20	96,279	43,940				2,304	1,051	68	31	2,372	1,082		
	H44	21	100,465	44,087				2,304	1,011	70	31	2,374	1,042		
	H45	22	104,651	44,158				2,304	972	71	30	2,375	1,002		
H46	23	108,837	44,158				2,304	935	73	30	2,377	964			
H47	24	113,023	44,093				2,304	899	75	29	2,379	928			
H48	25	117,209	43,967				2,304	864	77	29	2,381	893			
H49	26	121,395	43,786				2,304	831	78	28	2,382	859			
評価期間	H50	27	125,581	43,554					122	42	122	42			
	H51	28	125,581	41,878					122	41	122	41			
	H52	29	125,581	40,268					122	39	122	39			
	H53	30	125,581	38,719					122	37	122	37			
	H54	31	125,581	37,230					122	36	122	36			
	H55	32	125,581	35,798					122	35	122	35			
	H56	33	125,581	34,421					122	33	122	33			
	H57	34	125,581	33,097					122	32	122	32			
	H58	35	125,581	31,824					122	31	122	31			
	H59	36	125,581	30,600					122	30	122	30			
	H60	37	125,581	29,423					122	28	122	28			
	H61	38	125,581	28,292					122	27	122	27			
	H62	39	125,581	27,203					122	26	122	26			
	H63	40	125,581	26,157					122	25	122	25			
	H64	41	125,581	25,151					122	24	122	24			
	H65	42	125,581	24,184					122	23	122	23			
	H66	43	125,581	23,254					122	23	122	23			
	H67	44	125,581	22,359					122	22	122	22			
	H68	45	125,581	21,499					122	21	122	21			
	H69	46	125,581	20,672					122	20	122	20			
	H70	47	125,581	19,877					122	19	122	19			
	H71	48	125,581	19,113					122	18	122	18			
	H72	49	125,581	18,378					122	18	122	18			
	H73	50	125,581	17,671					122	17	122	17			
	H74	51	125,581	16,991					122	16	122	16			
	H75	52	125,581	16,338					122	16	122	16			
	H76	53	125,581	15,709					122	15	122	15			
	H77	54	125,581	15,105					122	15	122	15			
	H78	55	125,581	14,524					122	14	122	14			
	H79	56	125,581	13,966					122	14	122	14			
H80	57	125,581	13,428					122	13	122	13				
H81	58	125,581	12,912					122	12	122	12				
H82	59	125,581	12,415					122	12	122	12				
H83	60	125,581	11,938					122	12	122	12				
H84	61	125,581	11,479					122	11	122	11				
H85	62	125,581	11,037					122	11	122	11				
H86	63	125,581	10,613					122	10	122	10				
H87	64	125,581	10,204					122	10	122	10				
H88	65	125,581	9,812					122	9	122	9				
H89	66	125,581	9,435					122	9	122	9				
H90	67	125,581	9,072					122	9	122	9				
H91	68	125,581	8,723					122	8	122	8				
H92	69	125,581	8,387					122	8	122	8				
H93	70	125,581	8,065					122	8	122	8				
H94	71	125,581	7,755					122	8	122	8				
H95	72	125,581	7,456					122	7	122	7				
H96	73	125,581	7,170					122	7	122	7				
H97	74	125,581	6,894					122	7	122	7				
H98	75	125,581	6,629					122	6	122	6				
H99	76	125,581	6,374					122	6	122	6				
合計			8,099,982	1,957,666	912	1,958,578	66,943	44,566	8,852	2,766	75,794	47,332	41.4	1,911,246	

百万円

年次	t	便 益			費 用				費用便益比 B/C	純現在価値 B-C			
		便 益	①	②	建設費		維持管理費				③	④	
			現在価値	残存価値	①+②	費用	現在価値	費用			現在価値	費用	現在価値
H24	1	0	0		1,246	1,198	0	0	1,246	1,198			
H25	2	372	344		1,650	1,526	282	261	1,932	1,786			
H26	3	743	661		2,285	2,031	145	129	2,430	2,160			
H27	4	1,115	953		2,133	1,823	8	7	2,141	1,830			
H28	5	1,487	1,222		1,683	1,383	12	10	1,695	1,393			
H29	6	1,858	1,469		2,304	1,821	14	11	2,318	1,832			
H30	7	7,407	5,629		2,304	1,751	16	12	2,320	1,763			
H31	8	12,956	9,466		2,304	1,683	18	13	2,322	1,697			
H32	9	18,504	13,001		2,304	1,619	20	14	2,324	1,632			
H33	10	24,053	16,249		2,304	1,556	21	14	2,325	1,571			
H34	11	29,601	19,229		2,304	1,497	23	15	2,327	1,512			
H35	12	35,150	21,955		2,304	1,439	25	16	2,329	1,455			
H36	13	40,699	24,443		2,304	1,384	27	16	2,330	1,400			
H37	14	46,247	26,707		2,304	1,330	28	16	2,332	1,347			
H38	15	51,796	28,760		2,304	1,279	30	17	2,334	1,296			
H39	16	57,345	30,617		2,304	1,230	32	17	2,336	1,247			
H40	17	62,893	32,288		2,304	1,183	124	63	2,427	1,246			
H41	18	68,442	33,785		2,304	1,137	185	91	2,489	1,229			
H42	19	73,991	35,119		2,304	1,094	337	160	2,641	1,253			
H43	20	79,539	36,301		2,304	1,051	39	18	2,343	1,069			
H44	21	85,088	37,339		2,304	1,011	40	18	2,344	1,029			
H45	22	90,636	38,245		2,304	972	42	18	2,346	990			
H46	23	96,185	39,025		2,304	935	44	18	2,348	953			
H47	24	101,734	39,688		2,304	899	46	18	2,349	917			
H48	25	107,282	40,243		2,304	864	47	18	2,351	882			
H49	26	112,831	40,697		2,304	831	49	18	2,353	849			
H50	27	118,380	41,056				92	32	92	32			
H51	28	118,380	39,477				92	31	92	31			
H52	29	118,380	37,959				92	30	92	30			
H53	30	118,380	36,499				92	28	92	28			
H54	31	118,380	35,095				92	27	92	27			
H55	32	118,380	33,745				92	26	92	26			
H56	33	118,380	32,447				92	25	92	25			
H57	34	118,380	31,199				92	24	92	24			
H58	35	118,380	29,999				92	23	92	23			
H59	36	118,380	28,845				92	22	92	22			
H60	37	118,380	27,736				92	22	92	22			
H61	38	118,380	26,669				92	21	92	21			
H62	39	118,380	25,643				92	20	92	20			
H63	40	118,380	24,657				92	19	92	19			
H64	41	118,380	23,709				92	18	92	18			
H65	42	118,380	22,797				92	18	92	18			
H66	43	118,380	21,920				92	17	92	17			
H67	44	118,380	21,077				92	16	92	16			
H68	45	118,380	20,266				92	16	92	16			
H69	46	118,380	19,487				92	15	92	15			
H70	47	118,380	18,737				92	15	92	15			
H71	48	118,380	18,017				92	14	92	14			
H72	49	118,380	17,324				92	13	92	13			
H73	50	118,380	16,657				92	13	92	13			
H74	51	118,380	16,017				92	12	92	12			
H75	52	118,380	15,401				92	12	92	12			
H76	53	118,380	14,808				92	12	92	12			
H77	54	118,380	14,239				92	11	92	11			
H78	55	118,380	13,691				92	11	92	11			
H79	56	118,380	13,165				92	10	92	10			
H80	57	118,380	12,658				92	10	92	10			
H81	58	118,380	12,171				92	9	92	9			
H82	59	118,380	11,703				92	9	92	9			
H83	60	118,380	11,253				92	9	92	9			
H84	61	118,380	10,820				92	8	92	8			
H85	62	118,380	10,404				92	8	92	8			
H86	63	118,380	10,004				92	8	92	8			
H87	64	118,380	9,619				92	7	92	7			
H88	65	118,380	9,249				92	7	92	7			
H89	66	118,380	8,894				92	7	92	7			
H90	67	118,380	8,552				92	7	92	7			
H91	68	118,380	8,223				92	6	92	6			
H92	69	118,380	7,906				92	6	92	6			
H93	70	118,380	7,602				92	6	92	6			
H94	71	118,380	7,310				92	6	92	6			
H95	72	118,380	7,029				92	5	92	5			
H96	73	118,380	6,758				92	5	92	5			
H97	74	118,380	6,498				92	5	92	5			
H98	75	118,380	6,249				92	5	92	5			
H99	76	118,380	6,008				92	5	92	5			
合計		7,126,931	1,490,684	861	1,491,545	57,378	34,527	6,260	1,721	63,638	36,248	41.1	1,455,297

百万円

年次	t	便 益				費 用				費用便益比 B/C	純現在価値 B-C		
		便 益	①			建設費		維持管理費				③	④
			現在価値	残存価値	①+②	費用	現在価値	費用	現在価値				
H24	1	0	0			1,371	1,318	0	0	1,371	1,318		
H25	2	372	344			1,815	1,678	282	261	2,097	1,939		
H26	3	743	661			2,514	2,234	145	129	2,658	2,363		
H27	4	1,115	953			2,346	2,006	8	7	2,355	2,013		
H28	5	1,487	1,222			1,851	1,522	12	10	1,863	1,531		
H29	6	1,858	1,469			2,534	2,003	14	11	2,549	2,014		
H30	7	7,407	5,629			2,534	1,926	16	12	2,550	1,938		
H31	8	12,956	9,466			2,534	1,852	18	13	2,552	1,865		
H32	9	18,504	13,001			2,534	1,781	20	14	2,554	1,794		
H33	10	24,053	16,249			2,534	1,712	21	14	2,556	1,727		
H34	11	29,601	19,229			2,534	1,646	23	15	2,557	1,661		
H35	12	35,150	21,955			2,534	1,583	25	16	2,559	1,598		
H36	13	40,699	24,443			2,534	1,522	27	16	2,561	1,538		
H37	14	46,247	26,707			2,534	1,463	28	16	2,563	1,480		
H38	15	51,796	28,760			2,534	1,407	30	17	2,564	1,424		
H39	16	57,345	30,617			2,534	1,353	32	17	2,566	1,370		
H40	17	62,893	32,288			2,534	1,301	124	63	2,658	1,364		
H41	18	68,442	33,785			2,534	1,251	185	91	2,719	1,342		
H42	19	73,991	35,119			2,534	1,203	337	160	2,871	1,363		
H43	20	79,539	36,301			2,534	1,157	39	18	2,573	1,174		
H44	21	85,088	37,339			2,534	1,112	40	18	2,575	1,130		
H45	22	90,636	38,245			2,534	1,069	42	18	2,576	1,087		
H46	23	96,185	39,025			2,534	1,028	44	18	2,578	1,046		
H47	24	101,734	39,688			2,534	989	46	18	2,580	1,006		
H48	25	107,282	40,243			2,534	951	47	18	2,582	968		
H49	26	112,831	40,697			2,534	914	49	18	2,583	932		
H50	27	118,380	41,056					92	32	92	32		
H51	28	118,380	39,477					92	31	92	31		
H52	29	118,380	37,959					92	30	92	30		
H53	30	118,380	36,499					92	28	92	28		
H54	31	118,380	35,095					92	27	92	27		
H55	32	118,380	33,745					92	26	92	26		
H56	33	118,380	32,447					92	25	92	25		
H57	34	118,380	31,199					92	24	92	24		
H58	35	118,380	29,999					92	23	92	23		
H59	36	118,380	28,845					92	22	92	22		
H60	37	118,380	27,736					92	22	92	22		
H61	38	118,380	26,669					92	21	92	21		
H62	39	118,380	25,643					92	20	92	20		
H63	40	118,380	24,657					92	19	92	19		
H64	41	118,380	23,709					92	18	92	18		
H65	42	118,380	22,797					92	18	92	18		
H66	43	118,380	21,920					92	17	92	17		
H67	44	118,380	21,077					92	16	92	16		
H68	45	118,380	20,266					92	16	92	16		
H69	46	118,380	19,487					92	15	92	15		
H70	47	118,380	18,737					92	15	92	15		
H71	48	118,380	18,017					92	14	92	14		
H72	49	118,380	17,324					92	13	92	13		
H73	50	118,380	16,657					92	13	92	13		
H74	51	118,380	16,017					92	12	92	12		
H75	52	118,380	15,401					92	12	92	12		
H76	53	118,380	14,808					92	12	92	12		
H77	54	118,380	14,239					92	11	92	11		
H78	55	118,380	13,691					92	11	92	11		
H79	56	118,380	13,165					92	10	92	10		
H80	57	118,380	12,658					92	10	92	10		
H81	58	118,380	12,171					92	9	92	9		
H82	59	118,380	11,703					92	9	92	9		
H83	60	118,380	11,253					92	9	92	9		
H84	61	118,380	10,820					92	8	92	8		
H85	62	118,380	10,404					92	8	92	8		
H86	63	118,380	10,004					92	8	92	8		
H87	64	118,380	9,619					92	7	92	7		
H88	65	118,380	9,249					92	7	92	7		
H89	66	118,380	8,894					92	7	92	7		
H90	67	118,380	8,552					92	7	92	7		
H91	68	118,380	8,223					92	6	92	6		
H92	69	118,380	7,906					92	6	92	6		
H93	70	118,380	7,602					92	6	92	6		
H94	71	118,380	7,310					92	6	92	6		
H95	72	118,380	7,029					92	5	92	5		
H96	73	118,380	6,758					92	5	92	5		
H97	74	118,380	6,498					92	5	92	5		
H98	75	118,380	6,249					92	5	92	5		
H99	76	118,380	6,008					92	5	92	5		
合計		7,126,931	1,490,684	947	1,491,631	63,116	37,980	6,260	1,721	69,376	39,701	37.6	1,451,930

百万円

年次	t	便 益				費 用				費用便益比 B/C	純現在価値 B-C		
		便 益	①			建設費		維持管理費				③	④
			現在価値	残存価値	①+②	費用	現在価値	費用	現在価値				
H24	1	0	0			1,121	1,078	0	0	1,121	1,078		
H25	2	372	344			1,485	1,373	282	261	1,767	1,634		
H26	3	743	661			2,057	1,828	145	129	2,201	1,957		
H27	4	1,115	953			1,920	1,641	8	7	1,928	1,648		
H28	5	1,487	1,222			1,515	1,245	12	10	1,526	1,255		
H29	6	1,858	1,469			2,073	1,639	14	11	2,088	1,650		
H30	7	7,407	5,629			2,073	1,576	16	12	2,090	1,588		
H31	8	12,956	9,466			2,073	1,515	18	13	2,091	1,528		
H32	9	18,504	13,001			2,073	1,457	20	14	2,093	1,471		
H33	10	24,053	16,249			2,073	1,401	21	14	2,095	1,415		
H34	11	29,601	19,229			2,073	1,347	23	15	2,097	1,362		
H35	12	35,150	21,955			2,073	1,295	25	16	2,098	1,311		
H36	13	40,699	24,443			2,073	1,245	27	16	2,100	1,261		
H37	14	46,247	26,707			2,073	1,197	28	16	2,102	1,214		
H38	15	51,796	28,760			2,073	1,151	30	17	2,104	1,168		
H39	16	57,345	30,617			2,073	1,107	32	17	2,105	1,124		
H40	17	62,893	32,288			2,073	1,064	124	63	2,197	1,128		
H41	18	68,442	33,785			2,073	1,024	185	91	2,259	1,115		
H42	19	73,991	35,119			2,073	984	337	160	2,410	1,144		
H43	20	79,539	36,301			2,073	946	39	18	2,112	964		
H44	21	85,088	37,339			2,073	910	40	18	2,114	928		
H45	22	90,636	38,245			2,073	875	42	18	2,116	893		
H46	23	96,185	39,025			2,073	841	44	18	2,117	859		
H47	24	101,734	39,688			2,073	809	46	18	2,119	827		
H48	25	107,282	40,243			2,073	778	47	18	2,121	796		
H49	26	112,831	40,697			2,073	748	49	18	2,123	766		
H50	27	118,380	41,056					92	32	92	32		
H51	28	118,380	39,477					92	31	92	31		
H52	29	118,380	37,959					92	30	92	30		
H53	30	118,380	36,499					92	28	92	28		
H54	31	118,380	35,095					92	27	92	27		
H55	32	118,380	33,745					92	26	92	26		
H56	33	118,380	32,447					92	25	92	25		
H57	34	118,380	31,199					92	24	92	24		
H58	35	118,380	29,999					92	23	92	23		
H59	36	118,380	28,845					92	22	92	22		
H60	37	118,380	27,736					92	22	92	22		
H61	38	118,380	26,669					92	21	92	21		
H62	39	118,380	25,643					92	20	92	20		
H63	40	118,380	24,657					92	19	92	19		
H64	41	118,380	23,709					92	18	92	18		
H65	42	118,380	22,797					92	18	92	18		
H66	43	118,380	21,920					92	17	92	17		
H67	44	118,380	21,077					92	16	92	16		
H68	45	118,380	20,266					92	16	92	16		
H69	46	118,380	19,487					92	15	92	15		
H70	47	118,380	18,737					92	15	92	15		
H71	48	118,380	18,017					92	14	92	14		
H72	49	118,380	17,324					92	13	92	13		
H73	50	118,380	16,657					92	13	92	13		
H74	51	118,380	16,017					92	12	92	12		
H75	52	118,380	15,401					92	12	92	12		
H76	53	118,380	14,808					92	12	92	12		
H77	54	118,380	14,239					92	11	92	11		
H78	55	118,380	13,691					92	11	92	11		
H79	56	118,380	13,165					92	10	92	10		
H80	57	118,380	12,658					92	10	92	10		
H81	58	118,380	12,171					92	9	92	9		
H82	59	118,380	11,703					92	9	92	9		
H83	60	118,380	11,253					92	9	92	9		
H84	61	118,380	10,820					92	8	92	8		
H85	62	118,380	10,404					92	8	92	8		
H86	63	118,380	10,004					92	8	92	8		
H87	64	118,380	9,619					92	7	92	7		
H88	65	118,380	9,249					92	7	92	7		
H89	66	118,380	8,894					92	7	92	7		
H90	67	118,380	8,552					92	7	92	7		
H91	68	118,380	8,223					92	6	92	6		
H92	69	118,380	7,906					92	6	92	6		
H93	70	118,380	7,602					92	6	92	6		
H94	71	118,380	7,310					92	6	92	6		
H95	72	118,380	7,029					92	5	92	5		
H96	73	118,380	6,758					92	5	92	5		
H97	74	118,380	6,498					92	5	92	5		
H98	75	118,380	6,249					92	5	92	5		
H99	76	118,380	6,008					92	5	92	5		
合計		7,126,931	1,490,684	774	1,491,458	51,640	31,074	6,260	1,721	57,900	32,795	45.5	1,458,663

百万円

年次	t	便 益				費 用				費用便益比 B/C	純現在価値 B-C		
		便 益	①			建設費		維持管理費				③	
			現在価値	残存価値	①+②	費用	現在価値	費用	現在価値			費用	現在価値
H24	1	0	0			1,117	1,074	0	0	1,117	1,074		
H25	2	372	344			1,438	1,329	282	261	1,720	1,590		
H26	3	743	661			1,917	1,704	145	129	2,062	1,833		
H27	4	1,115	953			1,960	1,675	8	7	1,968	1,682		
H28	5	1,487	1,222			1,695	1,393	12	10	1,707	1,403		
H29	6	1,858	1,469			1,744	1,379	14	11	1,759	1,390		
H30	7	6,713	5,102			2,066	1,570	16	12	2,082	1,582		
H31	8	11,568	8,453			2,066	1,509	18	13	2,083	1,522		
H32	9	16,423	11,539			2,066	1,451	20	14	2,085	1,465		
H33	10	21,278	14,375			2,066	1,395	21	14	2,087	1,410		
H34	11	26,134	16,976			2,066	1,342	23	15	2,089	1,357		
H35	12	30,989	19,355			2,066	1,290	25	16	2,090	1,306		
H36	13	35,844	21,527			2,066	1,241	27	16	2,092	1,256		
H37	14	40,699	23,502			2,066	1,193	28	16	2,094	1,209		
H38	15	45,554	25,294			2,066	1,147	30	17	2,096	1,164		
H39	16	50,409	26,914			2,066	1,103	32	17	2,097	1,120		
H40	17	55,264	28,371			2,066	1,060	124	63	2,189	1,124		
H41	18	60,119	29,676			2,066	1,020	185	91	2,251	1,111		
H42	19	64,974	30,839			2,066	980	337	160	2,402	1,140		
H43	20	69,829	31,869			2,066	943	39	18	2,104	960		
H44	21	74,684	32,774			2,066	906	40	18	2,106	924		
H45	22	79,539	33,562			2,066	872	42	18	2,108	889		
H46	23	84,394	34,241			2,066	838	44	18	2,109	856		
H47	24	89,249	34,818			2,066	806	46	18	2,111	824		
H48	25	94,104	35,300			2,066	775	47	18	2,113	793		
H49	26	98,959	35,694			2,066	745	49	18	2,115	763		
H50	27	103,814	36,005			2,066	716	92	32	2,158	748		
H51	28	108,669	36,239			2,066	689	92	31	2,158	720		
H52	29	113,525	36,402			2,066	662	92	30	2,158	692		
H53	30	118,380	36,499					92	28	92	28		
H54	31	118,380	35,095					92	27	92	27		
H55	32	118,380	33,745					92	26	92	26		
H56	33	118,380	32,447					92	25	92	25		
H57	34	118,380	31,199					92	24	92	24		
H58	35	118,380	29,999					92	23	92	23		
H59	36	118,380	28,845					92	22	92	22		
H60	37	118,380	27,736					92	22	92	22		
H61	38	118,380	26,669					92	21	92	21		
H62	39	118,380	25,643					92	20	92	20		
H63	40	118,380	24,657					92	19	92	19		
H64	41	118,380	23,709					92	18	92	18		
H65	42	118,380	22,797					92	18	92	18		
H66	43	118,380	21,920					92	17	92	17		
H67	44	118,380	21,077					92	16	92	16		
H68	45	118,380	20,266					92	16	92	16		
H69	46	118,380	19,487					92	15	92	15		
H70	47	118,380	18,737					92	15	92	15		
H71	48	118,380	18,017					92	14	92	14		
H72	49	118,380	17,324					92	13	92	13		
H73	50	118,380	16,657					92	13	92	13		
H74	51	118,380	16,017					92	12	92	12		
H75	52	118,380	15,401					92	12	92	12		
H76	53	118,380	14,808					92	12	92	12		
H77	54	118,380	14,239					92	11	92	11		
H78	55	118,380	13,691					92	11	92	11		
H79	56	118,380	13,165					92	10	92	10		
H80	57	118,380	12,658					92	10	92	10		
H81	58	118,380	12,171					92	9	92	9		
H82	59	118,380	11,703					92	9	92	9		
H83	60	118,380	11,253					92	9	92	9		
H84	61	118,380	10,820					92	8	92	8		
H85	62	118,380	10,404					92	8	92	8		
H86	63	118,380	10,004					92	8	92	8		
H87	64	118,380	9,619					92	7	92	7		
H88	65	118,380	9,249					92	7	92	7		
H89	66	118,380	8,894					92	7	92	7		
H90	67	118,380	8,552					92	7	92	7		
H91	68	118,380	8,223					92	6	92	6		
H92	69	118,380	7,906					92	6	92	6		
H93	70	118,380	7,602					92	6	92	6		
H94	71	118,380	7,310					92	6	92	6		
H95	72	118,380	7,029					92	5	92	5		
H96	73	118,380	6,758					92	5	92	5		
H97	74	118,380	6,498					92	5	92	5		
H98	75	118,380	6,249					92	5	92	5		
H99	76	118,380	6,008					92	5	92	5		
H100	77	118,380	5,777					92	4	92	4		
H101	78	118,380	5,555					92	4	92	4		
H102	79	118,380	5,341					92	4	92	4		
合計		7,307,288	1,428,908	765	1,429,673	57,378	32,807	6,536	1,734	63,914	34,541	41.4	1,395,132

百万円

年次	t	便 益			費 用				費用便益比 B/C	純現在価値 B-C			
		便 益	①	②	建設費		維持管理費				③	④	
			現在価値	残存価値	①+②	費 用	現在価値	費 用			現在価値	費 用	現在価値
H24	1	0	0		1,461	1,405	0	0	1,461	1,405			
H25	2	372	344		2,031	1,878	282	261	2,313	2,138			
H26	3	743	661		2,524	2,243	145	129	2,668	2,372			
H27	4	1,115	953		2,176	1,860	8	7	2,185	1,868			
H28	5	1,487	1,222		2,307	1,897	12	10	2,319	1,906			
H29	6	1,858	1,469		2,604	2,058	14	11	2,619	2,070			
H30	7	8,332	6,331		2,604	1,979	16	12	2,621	1,991			
H31	8	14,805	10,818		2,604	1,903	18	13	2,622	1,916			
H32	9	21,278	14,950		2,604	1,830	20	14	2,624	1,844			
H33	10	27,752	18,748		2,604	1,759	21	14	2,626	1,774			
H34	11	34,225	22,232		2,604	1,692	23	15	2,627	1,707			
H35	12	40,699	25,420		2,604	1,627	25	16	2,629	1,642			
H36	13	47,172	28,330		2,604	1,564	27	16	2,631	1,580			
H37	14	53,646	30,979		2,604	1,504	28	16	2,633	1,520			
H38	15	60,119	33,382		2,604	1,446	40	22	2,645	1,469			
H39	16	66,592	35,554		2,604	1,390	42	23	2,647	1,413			
H40	17	73,066	37,510		2,604	1,337	44	23	2,648	1,360			
H41	18	79,539	39,263		2,604	1,286	46	23	2,650	1,308			
H42	19	86,013	40,825		2,604	1,236	47	22	2,652	1,259			
H43	20	92,486	42,209		2,604	1,189	49	22	2,653	1,211			
H44	21	98,959	43,427		2,604	1,143	92	40	2,696	1,183			
H45	22	105,433	44,488		2,604	1,099	92	39	2,696	1,138			
H46	23	111,906	45,403		2,604	1,057	92	37	2,696	1,094			
H47	24	118,380	46,182				92	36	92	36			
H48	25	118,380	44,406				92	35	92	35			
H49	26	118,380	42,698				92	33	92	33			
H50	27	118,380	41,056				92	32	92	32			
H51	28	118,380	39,477				92	31	92	31			
H52	29	118,380	37,959				92	30	92	30			
H53	30	118,380	36,499				92	28	92	28			
H54	31	118,380	35,095				92	27	92	27			
H55	32	118,380	33,745				92	26	92	26			
H56	33	118,380	32,447				92	25	92	25			
H57	34	118,380	31,199				92	24	92	24			
H58	35	118,380	29,999				92	23	92	23			
H59	36	118,380	28,845				92	22	92	22			
H60	37	118,380	27,736				92	22	92	22			
H61	38	118,380	26,669				92	21	92	21			
H62	39	118,380	25,643				92	20	92	20			
H63	40	118,380	24,657				92	19	92	19			
H64	41	118,380	23,709				92	18	92	18			
H65	42	118,380	22,797				92	18	92	18			
H66	43	118,380	21,920				92	17	92	17			
H67	44	118,380	21,077				92	16	92	16			
H68	45	118,380	20,266				92	16	92	16			
H69	46	118,380	19,487				92	15	92	15			
H70	47	118,380	18,737				92	15	92	15			
H71	48	118,380	18,017				92	14	92	14			
H72	49	118,380	17,324				92	13	92	13			
H73	50	118,380	16,657				92	13	92	13			
H74	51	118,380	16,017				92	12	92	12			
H75	52	118,380	15,401				92	12	92	12			
H76	53	118,380	14,808				92	12	92	12			
H77	54	118,380	14,239				92	11	92	11			
H78	55	118,380	13,691				92	11	92	11			
H79	56	118,380	13,165				92	10	92	10			
H80	57	118,380	12,658				92	10	92	10			
H81	58	118,380	12,171				92	9	92	9			
H82	59	118,380	11,703				92	9	92	9			
H83	60	118,380	11,253				92	9	92	9			
H84	61	118,380	10,820				92	8	92	8			
H85	62	118,380	10,404				92	8	92	8			
H86	63	118,380	10,004				92	8	92	8			
H87	64	118,380	9,619				92	7	92	7			
H88	65	118,380	9,249				92	7	92	7			
H89	66	118,380	8,894				92	7	92	7			
H90	67	118,380	8,552				92	7	92	7			
H91	68	118,380	8,223				92	6	92	6			
H92	69	118,380	7,906				92	6	92	6			
H93	70	118,380	7,602				92	6	92	6			
H94	71	118,380	7,310				92	6	92	6			
H95	72	118,380	7,029				92	5	92	5			
H96	73	118,380	6,758				92	5	92	5			
合計		6,946,575	1,556,301	969	1,557,270	57,378	36,381	5,790	1,589	63,168	37,970	41.0	1,519,300

百万円

年次	t	便 益				費 用				費用便益比 B/C	純現在価値 B-C		
		便 益	①			建設費		維持管理費				③	
			現在価値	残存価値	①+②	費用	現在価値	費用	現在価値			費用	現在価値
H24	1	0	0			1,246	1,198	0	0	1,246	1,198		
H25	2	408	377			1,650	1,526	282	261	1,932	1,786		
H26	3	816	726			2,285	2,031	145	129	2,430	2,160		
H27	4	1,224	1,047			2,133	1,823	8	7	2,141	1,830		
H28	5	1,632	1,342			1,683	1,383	12	10	1,695	1,393		
H29	6	2,041	1,613			2,304	1,821	14	11	2,318	1,832		
H30	7	8,131	6,179			2,304	1,751	16	12	2,320	1,763		
H31	8	14,222	10,392			2,304	1,683	18	13	2,322	1,697		
H32	9	20,313	14,272			2,304	1,619	20	14	2,324	1,632		
H33	10	26,404	17,837			2,304	1,556	21	14	2,325	1,571		
H34	11	32,495	21,108			2,304	1,497	23	15	2,327	1,512		
H35	12	38,586	24,100			2,304	1,439	25	16	2,329	1,455		
H36	13	44,676	26,831			2,304	1,384	27	16	2,330	1,400		
H37	14	50,767	29,317			2,304	1,330	28	16	2,332	1,347		
H38	15	56,858	31,571			2,304	1,279	30	17	2,334	1,296		
H39	16	62,949	33,609			2,304	1,230	32	17	2,336	1,247		
H40	17	69,040	35,443			2,304	1,183	124	63	2,427	1,246		
H41	18	75,130	37,087			2,304	1,137	185	91	2,489	1,229		
H42	19	81,221	38,551			2,304	1,094	337	160	2,641	1,253		
H43	20	87,312	39,848			2,304	1,051	39	18	2,343	1,069		
H44	21	93,403	40,988			2,304	1,011	40	18	2,344	1,029		
H45	22	99,494	41,982			2,304	972	42	18	2,346	990		
H46	23	105,585	42,838			2,304	935	44	18	2,348	953		
H47	24	111,675	43,567			2,304	899	46	18	2,349	917		
H48	25	117,766	44,176			2,304	864	47	18	2,351	882		
H49	26	123,857	44,674			2,304	831	49	18	2,353	849		
H50	27	129,948	45,068					92	32	92	32		
H51	28	129,948	43,335					92	31	92	31		
H52	29	129,948	41,668					92	30	92	30		
H53	30	129,948	40,065					92	28	92	28		
H54	31	129,948	38,524					92	27	92	27		
H55	32	129,948	37,043					92	26	92	26		
H56	33	129,948	35,618					92	25	92	25		
H57	34	129,948	34,248					92	24	92	24		
H58	35	129,948	32,931					92	23	92	23		
H59	36	129,948	31,664					92	22	92	22		
H60	37	129,948	30,446					92	22	92	22		
H61	38	129,948	29,275					92	21	92	21		
H62	39	129,948	28,149					92	20	92	20		
H63	40	129,948	27,067					92	19	92	19		
H64	41	129,948	26,026					92	18	92	18		
H65	42	129,948	25,025					92	18	92	18		
H66	43	129,948	24,062					92	17	92	17		
H67	44	129,948	23,137					92	16	92	16		
H68	45	129,948	22,247					92	16	92	16		
H69	46	129,948	21,391					92	15	92	15		
H70	47	129,948	20,568					92	15	92	15		
H71	48	129,948	19,777					92	14	92	14		
H72	49	129,948	19,017					92	13	92	13		
H73	50	129,948	18,285					92	13	92	13		
H74	51	129,948	17,582					92	12	92	12		
H75	52	129,948	16,906					92	12	92	12		
H76	53	129,948	16,256					92	12	92	12		
H77	54	129,948	15,630					92	11	92	11		
H78	55	129,948	15,029					92	11	92	11		
H79	56	129,948	14,451					92	10	92	10		
H80	57	129,948	13,895					92	10	92	10		
H81	58	129,948	13,361					92	9	92	9		
H82	59	129,948	12,847					92	9	92	9		
H83	60	129,948	12,353					92	9	92	9		
H84	61	129,948	11,878					92	8	92	8		
H85	62	129,948	11,421					92	8	92	8		
H86	63	129,948	10,982					92	8	92	8		
H87	64	129,948	10,559					92	7	92	7		
H88	65	129,948	10,153					92	7	92	7		
H89	66	129,948	9,763					92	7	92	7		
H90	67	129,948	9,387					92	7	92	7		
H91	68	129,948	9,026					92	6	92	6		
H92	69	129,948	8,679					92	6	92	6		
H93	70	129,948	8,345					92	6	92	6		
H94	71	129,948	8,024					92	6	92	6		
H95	72	129,948	7,716					92	5	92	5		
H96	73	129,948	7,419					92	5	92	5		
H97	74	129,948	7,133					92	5	92	5		
H98	75	129,948	6,859					92	5	92	5		
H99	76	129,948	6,595					92	5	92	5		
合計		7,823,401	1,636,363	861	1,637,224	57,378	34,527	6,260	1,721	63,638	36,248	45.2	1,600,976

百万円

年次	t	便 益				費 用				費用便益比 B/C	純現在価値 B-C		
		便 益	①			建設費		維持管理費				③	④
			現在価値	残存価値	①+②	費用	現在価値	費用	現在価値				
H24	1	0	0			1,246	1,198	0	0	1,246	1,198		
H25	2	335	310			1,650	1,526	282	261	1,932	1,786		
H26	3	670	596			2,285	2,031	145	129	2,430	2,160		
H27	4	1,006	860			2,133	1,823	8	7	2,141	1,830		
H28	5	1,341	1,102			1,683	1,383	12	10	1,695	1,393		
H29	6	1,676	1,325			2,304	1,821	14	11	2,318	1,832		
H30	7	6,682	5,078			2,304	1,751	16	12	2,320	1,763		
H31	8	11,688	8,541			2,304	1,683	18	13	2,322	1,697		
H32	9	16,695	11,729			2,304	1,619	20	14	2,324	1,632		
H33	10	21,701	14,660			2,304	1,556	21	14	2,325	1,571		
H34	11	26,707	17,348			2,304	1,497	23	15	2,327	1,512		
H35	12	31,713	19,808			2,304	1,439	25	16	2,329	1,455		
H36	13	36,719	22,053			2,304	1,384	27	16	2,330	1,400		
H37	14	41,725	24,095			2,304	1,330	28	16	2,332	1,347		
H38	15	46,731	25,948			2,304	1,279	30	17	2,334	1,296		
H39	16	51,738	27,623			2,304	1,230	32	17	2,336	1,247		
H40	17	56,744	29,131			2,304	1,183	124	63	2,427	1,246		
H41	18	61,750	30,481			2,304	1,137	185	91	2,489	1,229		
H42	19	66,756	31,685			2,304	1,094	337	160	2,641	1,253		
H43	20	71,762	32,751			2,304	1,051	39	18	2,343	1,069		
H44	21	76,768	33,688			2,304	1,011	40	18	2,344	1,029		
H45	22	81,774	34,505			2,304	972	42	18	2,346	990		
H46	23	86,780	35,209			2,304	935	44	18	2,348	953		
H47	24	91,787	35,808			2,304	899	46	18	2,349	917		
H48	25	96,793	36,309			2,304	864	47	18	2,351	882		
H49	26	101,799	36,718			2,304	831	49	18	2,353	849		
H50	27	106,805	37,042					92	32	92	32		
H51	28	106,805	35,617					92	31	92	31		
H52	29	106,805	34,247					92	30	92	30		
H53	30	106,805	32,930					92	28	92	28		
H54	31	106,805	31,663					92	27	92	27		
H55	32	106,805	30,446					92	26	92	26		
H56	33	106,805	29,275					92	25	92	25		
H57	34	106,805	28,149					92	24	92	24		
H58	35	106,805	27,066					92	23	92	23		
H59	36	106,805	26,025					92	22	92	22		
H60	37	106,805	25,024					92	22	92	22		
H61	38	106,805	24,062					92	21	92	21		
H62	39	106,805	23,136					92	20	92	20		
H63	40	106,805	22,246					92	19	92	19		
H64	41	106,805	21,391					92	18	92	18		
H65	42	106,805	20,568					92	18	92	18		
H66	43	106,805	19,777					92	17	92	17		
H67	44	106,805	19,016					92	16	92	16		
H68	45	106,805	18,285					92	16	92	16		
H69	46	106,805	17,582					92	15	92	15		
H70	47	106,805	16,905					92	15	92	15		
H71	48	106,805	16,255					92	14	92	14		
H72	49	106,805	15,630					92	13	92	13		
H73	50	106,805	15,029					92	13	92	13		
H74	51	106,805	14,451					92	12	92	12		
H75	52	106,805	13,895					92	12	92	12		
H76	53	106,805	13,361					92	12	92	12		
H77	54	106,805	12,847					92	11	92	11		
H78	55	106,805	12,353					92	11	92	11		
H79	56	106,805	11,877					92	10	92	10		
H80	57	106,805	11,421					92	10	92	10		
H81	58	106,805	10,981					92	9	92	9		
H82	59	106,805	10,559					92	9	92	9		
H83	60	106,805	10,153					92	9	92	9		
H84	61	106,805	9,762					92	8	92	8		
H85	62	106,805	9,387					92	8	92	8		
H86	63	106,805	9,026					92	8	92	8		
H87	64	106,805	8,679					92	7	92	7		
H88	65	106,805	8,345					92	7	92	7		
H89	66	106,805	8,024					92	7	92	7		
H90	67	106,805	7,715					92	7	92	7		
H91	68	106,805	7,419					92	6	92	6		
H92	69	106,805	7,133					92	6	92	6		
H93	70	106,805	6,859					92	6	92	6		
H94	71	106,805	6,595					92	6	92	6		
H95	72	106,805	6,341					92	5	92	5		
H96	73	106,805	6,098					92	5	92	5		
H97	74	106,805	5,863					92	5	92	5		
H98	75	106,805	5,638					92	5	92	5		
H99	76	106,805	5,421					92	5	92	5		
合計		6,430,088	1,344,928	861	1,345,789	57,378	34,527	6,260	1,721	63,638	36,248	37.1	1,309,541